

1 250343

R

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-189-20,647 - 0000  
SE, SEC. 34, T 34 S, R 38 W/E

2540 feet from S section line  
1250 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5469

Lease Name Beavers "B" Well # 1

Operator: Anadarko Production Company  
Name & Address P.O. BOX 351  
Liberal Kansas 67901

County Stevens 101.24

Well Total Depth 3115 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8" feet 723'

Abandoned Oil Well Gas Well  Input Well SWD Well O&A

Other well as hereinafter indicated

Plugging Contractor The Western company of north America License Number  
Address Box AA Perryton Texas 79070

Company to plug at: Hour: 2:00pm Day: 30 Month: may Year: 1985

Plugging proposal received from Chuck Nelson

(company name) Anadarko (phone) 316-624-6253

were: 4 1/2" production casing is set at 3119' w/650sx PBD (3098) Perfs- 2992-3025 council  
grove.

Plugging instructions were to fill entire 4 1/2" casing w/260 sacks of 60/40 pozmix  
2% gel 3% cc cement. And if 8 5/8" annulus is open fill it with cement.

Plugging Proposal Received by Bob Tarbutton KDHE  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part None

Operations Completed: Hour: 2:45pm Day: 30 Month: May Year: 1985

ACTUAL PLUGGING REPORT Filled entire 4 1/2" casing w/260 sacks of 60/40 pozmix 2% gel 3% cc  
Filled 8 5/8 " annulus w/50 sacks of cement

welded a plate over 8 5/8"

Glen Barlow Witnessed the entire plugging procedure.

RECEIVED  
STATE CORPORATION COMMISSION

JUN 07 1985

Remarks:

(If additional description is necessary, use BACK of this report)  
CONSERVATION DIVISION  
Wichita, Kansas

(XXXX/XXXXXX) observe this plugging.

DATE 6-12-85 Did Not

Signed Richard M. Lacey  
(TECHNICIAN)

INV. NO. 8447

5-30