

1020776

15-129-10419-0000
API NUMBER 15- Spud date 12/15/54

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

C SW SW, SEC. 29, T 34 S, R 43 W, X
660 feet from S section line
4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4549
Operator: Anadarko Petroleum Corporation
Name & Address: P.O. Box 351
Liberal, KS 67905-0351

Lease Name Interstate Unit Well # 67
County Morton
Well Total Depth 4252 138.19 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 1200

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ O&A _____
Other well as hereinafter indicated _____

Plugging Contractor Sargent & Horton Plugging, Inc. License Number 31151
Address Rt. 1, Box 49BA, Tyrone, KS 73951-9731

Company to plug at: Hour: 1 p.m. Day: 6 Month: 7 Year: 19 94

Plugging proposal received from Don Horton
(company name) Sargent & Horton Plugging, Inc. (phone) 405-854-6575

Wells: 5 1/2" at 4252' w/250 sx cement, PBD 4222', Perfs at 4126-88'
1st plug set CIBP at 4100', run tubing and put 10 sx cement on top of CIBP, load 5 1/2" with mud,
2nd plug pump 50 sx cement at 1240',
3rd plug pump 35 sx cement at 650',
4th plug fill with cement from 40 to -4'.

Plugging Proposal Received by Glenn Barlow (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part None _____
Operations Completed: Hour: 4:30 p.m. Day: 7 Month: 7 Year: 19 94

ACTUAL PLUGGING REPORT 1st plug set CIBP at 4100', ran tubing and put 10 sx cement on top of CIBP, loaded 5 1/2" casing with mud,
2nd plug pumped 50 sx cement at 1240',
3rd plug pumped 35 sx cement at 650',
4th plug filled with cement from 40 to -4'.
Heavy mud between all plugs.

Remarks: Used common cement by Sargent & Horton's. Recovered 1240' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

I did / ~~xxxxxxx~~ observe this plugging.
Signed Glenn R. Barlow (TECHNICIAN)

RECEIVED
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
WICHITA, KANSAS
JUN 15 1994

40832
7-7