

To: 1 020649
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-129-20,607-0000 89R
NW NE NE, SEC. 29, T. 34 S, R. 43 W/E

TECHNICIAN'S PLUGGING REPORT

Operator License # 4549

4950 feet from S section line
990 feet from E section line
Lease Name Interstate Unit Well # 93A

Operator: Anadarko Petroleum Corporation
Name & Address P.O. Box 351
Liberal, KS 67905-0351

County Morton
Well Total Depth 4250 138.12 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 1193

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Sargent & Horton Plugging Inc. License Number 31151

Address Rt. 1, Box 49BA, Tyrone, OK 73951+9731

Company to plug at: Hour: 3 p.m. Day: 25 Month: 3 Year: 1993

Plugging proposal received from Don Horton

(company name) Sargent & Horton Plugging Inc. (phone) 405-854-6515

were: 5 1/2" at 4249' w/170 sx cement, PBSD 4096', Perfs at 4122-45'

1st plug pump 1 sx hulls and 25 sx cement at perfs, load hole with mud,

2nd plug pump 25 sx cement at 2400',

3rd plug pump 40 sx cement at 1220'. 4th plug pump 30 sx cement at 650',

5th plug pump 10 sx cement at 40 to -4'.

Plugging Proposal Received by Glenn Barlow
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part None _____

Operations Completed: Hour: 11:30 a.m. Day: 31 Month: 3 Year: 1993

ACTUAL PLUGGING REPORT 1st plug pumped 1 sx hulls and 25 sx cement at perfs, loaded hole with mud,

2nd plug pumped 25 sx cement at 2400',

3rd plug pumped 40 sx cement at 1220',

4th plug pumped 30 sx cement at 650',

5th plug pumped 10 sx cement at 40 to -4'.

Remarks: Used common cement by Sargent & Horton's. Recovered 2415' of 5 1/2" casing
(If additional description is necessary, use BACK of this form.)

I (did / ~~did not~~) observe this plugging.

4-8-93

37553

3-31

Signed Glenn R. Barlow
(TECHNICIAN)

RECEIVED
STATE CORPORATION COMMISSION
APR 7 1993
CONSERVATION DIVISION
Wichita, Kansas