

15-129-10447-0000

MAY 2 1 1987

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-Drill completion 2/19/55
C SE NW, SEC. 29, T 34 S, R 43 W/E
3300 feet from S section line
3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4549
Operator: Anadarko Petroleum Corporation
Name & Address P.O. Box 351
Liberal, KS 67901

Lease Name Interstate Unit Well # 57
County Morton 138.97
Well Total Depth 4276 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 1206

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Sargent's Casing Pulling Service License Number 6547

Address 620 S. Lincoln, Liberal, KS 67901

Company to plug at: Hour: 8 a.m. Day: 20 Month: 5 Year: 19 87

Plugging proposal received from Don Horton

(company name) Sargent's Casing Pulling Service (phone) 316-624-7455

were: 5 1/2" at 4276' PBD 4100' w/CIBP Perfs at 4167-76'

1st plug 20 sx cement on top of CIBP, 2nd plug on stub with 30 sx cement,

3rd plug at 1300-1000' with 40 sx cement,

4th plug at 650-400' with 35 sx cement,

5th plug at 10-40' with 10 sx cement.

Plugging Proposal Received by Steve Durrant
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 11:45 a.m. Day: 21 Month: 5 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug CIBP at 4100' with 20 sx cement on top,

2nd plug loaded hole-30 sx cement at 1810',

3rd plug 40 sx cement at 1300-1100',

4th plug 35 sx cement from 650-480',

5th plug 10 sx cement from 50-0'.

RECEIVED
STATE CORPORATION COMMISSION
MAY 27 1987

CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used common cement by Sargent's. Recovered 1810' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

~~I did not~~ observe this plugging.

Signed Glen R. Barlow
(TECHNICIAN)

5-28-87
This well was formerly Musgrove Petroleum Corporation Switzer #1.

NOV 17 1987
5-21
JUN 29 1987