

To: 1 020644
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

15-129-10445-0000
AP# NUMBER 15 - Docket # FE-21,363
C SE NE, SEC. 29, T. 34 S, R. 43 W XX

TECHNICIAN'S PLUGGING REPORT
Operator License # 4549

3300 feet from S section line
660 feet from E section line
Lease Name Interstate Unit Well # 59

Operator: Anadarko Petroleum Corp.
Name &
Address P.O. Box 351
Liberal, KS 67905-0351

County Morton
Well Total Depth 4357 141,60 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 1132

Abandoned Oil Well _____ Gas Well _____ Input Well X SMD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor Sargent & Horton Plugging, Inc. License Number 31151
Address Rt. 1, Box 49BA, Tyrone, OK 73951-9731

Company to plug at: Hour: 9:30 a.m. Day: 10 Month: 3 Year: 19 93

Plugging proposal received from Don Horton
(company name) Sargent & Horton Plugging, Inc. (phone) 405-854-6515

were: 5 1/2" at 4356', 2 3/8" fiberglass tubing at 4080', PBD 4225', Perfs at 4166-98'
1st plug pump 1 sx hulls and 70 sx cement down tubing, pressure up,
2nd plug pump 50 sx cement down annulus, pressure up,
Dig out and cut 8 5/8" & 5 1/2" off, fill both to surface and cap.

Plugging Proposal Received by Glenn R. Barlow
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X
Operations Completed: Hour: 4:30 p.m. Day: 10 Month: 3 Year: 19 93

ACTUAL PLUGGING REPORT 1st plug pumped 1 sx hulls and 70 sx cement down tubing, pressured up,
2nd plug pumped 50 sx cement down annulus, pressured up,
Dug out and cut 8 5/8" & 5 1/2" off. Filled both to surface and capped.

NOTE: 5 1/2" & 2 3/8" strings were cemented from total depth to surface.

RECEIVED
STATE CORPORATION COMMISSION
MAR 17 1993

Remarks: Used common cement by Sargent & Horton Casing Pulling. No casing recovery.
(if additional description is necessary, use BACK of this form.)

I (~~XXXX~~) did not observe this plugging.

Signed Glenn R. Barlow
(TECHNICIAN)

3-18-93
37486
3-10