

15-129-10420-0000 296

To: 1 020289
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-Docket #E-11,602
C SW SE, SEC. 29, T 34 S, R 43 W/E
660 feet from S section line
1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4549
Operator: Anadarko Petroleum Corporation
Name & Address: P.O. Box 351
Liberal, KS 67905-0351

Lease Name Interstate Unit Well # 69
County Morton 139.10
Well Total Depth 4280 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 1198

Abandoned Oil Well _____ Gas Well _____ Input Well SWD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor Sargent's Casing Pulling Service License Number 6547
Address P.O. Box 506, Liberal, KS 67905-0506

Company to plug at: Hour: 2 p.m. Day: 24 Month: 1 Year: 19 90

Plugging proposal received from Don Horton

(company name) Sargent's (phone) 316-624-7455

were: 5 1/2" at 4280' PBTD 4074' Perfs at 4212-32' CIBP in packer at 4074'

- 1st plug load hole with mud, spot 1 sx hulls and 20 sx cement at top of packer with tubing,
- 2nd plug pump 50 sx cement at 1245', displace with mud,
- 3rd plug spot 35 sx cement at 650-480', displace with mud,
- 4th plug spot 10 sx cement at 40 to -3'.

Plugging Proposal Received by Glenn R. Barlow (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part None _____

Operations Completed: Hour: 4:30 p.m. Day: 25 Month: 1 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug loaded hole with mud, spotted one sx hulls and 20 sx cement at top of packer with tubing,

2nd plug pumped 50 sx cement at 1245', displaced with mud,

3rd plug spotted 35 sx cement at 650'-480', displaced with mud,

4th plug spotted 10 sx cement at 40 to -3'.

RECEIVED
STATE CORPORATION COMMISSION
JAN 30 1990
CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used common cement by Sargent's. Recovered 1256' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

(I, the undersigned, hereby observe this plugging.)

Signed Glenn R. Barlow (TECHNICIAN)

DATE FEB 05 1990
NO. 27306
125