

To: 1 4-16
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15- 129-20,516-0000
SW NE NE, SEC. 29, T 34 S, R 43
4290 feet from S section line
990 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 4549
Operator: Anadarko Petroleum Corp.
Name:
Address: P.O. Box 351
Liberal, KS 67905-0351

Lease Name Roll "C" Well # 1
County Morton 40.11
Well Total Depth 1234 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 450

Abandoned Oil Well _____ Gas Well Input Well _____ SMD Well _____ O&A _____
Other well as hereinafter indicated _____

Plugging Contractor Sargents Casing Pulling Service License Number 6547
Address P.O. Box 506, Liberal, KS 67905-0506

Company to plug at: Hour: 8:30 a.m. Day: 16 Month: 4 Year: 1997

Plugging proposal received from Kirby Lillard
(company name) Sargents Casing Pulling Service (phone) 316-624-7455

Work: 5 1/2" at 1192' w/500 sx cement. Open hole
1st plug spot 2 sx hulls and 20 sx cement through tubing from 1234-1134',
2nd plug pull to 500' and spot 20 sx cement from 500-400',
3rd plug pull to 40' and spot 5 sx cement.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 11:30 a.m. Day: 16 Month: 4 Year: 1997

ACTUAL PLUGGING REPORT 1st plug ran tubing to 1190', loaded hole with mud and pumped 2 sx hulls and 25 sx cement, displaced to 1190-975',
2nd plug pulled tubing to 500' and pumped 20 sx cement and displaced to 500-328',
3rd plug pumped 5 sx cement from 40-0'.

Remarks: Used common cement by Sargents. No casing recovery.
(If additional description is necessary, use BACK of this form.)

I (did / was) observe this plugging.

4-23-97
48002
4-16

Signed Gary Winter (TECHNICIAN)