

To: 1 020646
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

15-129-00103-0000
API NUMBER 15- Drilled 4/6/54
C SW, SEC. 29, T. 34 S, R. 43 W XE

TECHNICIAN'S PLUGGING REPORT

Operator License # 4549

1320 feet from S section line
3960 feet from E section line

Operator: Anadarko Petroleum Corp.
Name & Address: P.O. Box 351
Liberal, KS 67905-0351

Lease Name Interstate Unit Well # 65
County Morton #148.59
Well Total Depth 4572 feet

Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 1237

Abandoned Oil Well Gas Well _____ Input Well _____ SMD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Sargent & Horton Plugging, Inc. License Number 31151
Address Rt. 1, Box 49BA, Tyrone, OK 73951-9731

Company to plug at: Hour: 2 p.m. Day: 17 Month: 3 Year: 19 93

Plugging proposal received from Don Horton

(company name) Sargent & Horton Plugging, Inc. (phone) 405-854-6515

were: 5 1/2" at 4560' w/650 sx cement, PBSD 4493', Perfs at 4192-4200'

1st plug pump 1 sx hulls and 25 sx cement at perfs with tubing and packer,

2nd plug pump 50 sx cement at 1260', 3rd plug pump 40 sx cement at 650',

4th plug pump 10' sx cement at 40-to -4'.

Plugging Proposal Received by Glenn Barlow (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part None _____

Operations Completed: Hour: 4 p.m. Day: 24 Month: 3 Year: 19 93

ACTUAL PLUGGING REPORT 1st plug pumped 1 sx hulls and 25 sx cement at perfs with tubing and packer,

2nd plug pumped 50 sx cement at 1260',

3rd plug pumped 40 sx cement at 650',

4th plug pumped 10 sx cement at 40 to -4'.

Used common cement by Sargent & Horton. Recovered 1450' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

(did not observe this plugging.)

Signed Glenn R Barlow (TECHNICIAN)

RECEIVED
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
WICHITA, KANSAS
APR 10 1993

4-2-93
37547
3-24