

To: 1100084  
STATE CORPORATION COMMISSION

API NUMBER 15- 129-21,023-0000

Wichita State Office Bldg. - PLUGGING SECTION App: SW NE NE, SEC. 28, T 34 S, R 43 W/EX  
130 S. Market, Room 2078  
Wichita, KS 67202

11-19

1250 feet from NXX section line  
1320 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4549  
Operator: Anadarko Petroleum Corporation  
Name:  
Address: P.O. Box 351  
Liberal, KS 67905-0351

Lease Name Goodthing Well # 1-28  
County Morton 102.37  
Well Total Depth 3150 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 1505

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ X Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ O&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Sargent & Horton Plugging, Inc. License Number 31151

Address Rt. 1, Box 49BA, Tyrone, OK 73951-9731

Company to plug at: Hour: 10 a.m. Day: 19 Month: 11 Year: 19 96

Plugging proposal received from Don Horton

(company name) Sargent & Horton Plugging, Inc. (phone) 405-854-6515

were: 4 1/2" at 3147' w/310 sx cement. CIBP @ 2814'. Perfs at 2954-3006, 2820-97, 2709-89'  
1st plug pump 25 sx cement from 2789-2589',

2nd plug pump 85 sx cement at 1655-1405',

3rd plug pump 50 sx cement at 600',

4th plug pump 10 sx cement at 40'.

Plugging Proposal Received by Gary Winters (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 2 p.m. Day: 19 Month: 11 Year: 19 96

ACTUAL PLUGGING REPORT 1st plug CIBP set at 2814' with 2 sx cement on top,

2nd plug displaced 25 sx cement from 2789-2589',

3rd plug pump 85 sx cement at 1655',

4th plug pump 40 sx cement at 600',

5th plug pump 10 sx cement at 40-0'.

11-27-96

Remarks: Used common cement by Sargent & Horton. Recovered 1450' of 4 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

I (did / ~~did not~~) observe this plugging.

Signed Gary Winters (TECHNICIAN)

47082  
11-19