

1 020774

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 129-20,341 - 0000  
NW NW NW , SEC. 28 , T 34 S, R 43  
250 feet from NX section line  
160 feet from WE section line

TECHNICIAN'S PLUGGING REPORT  
Operator License # 4549  
Operator: Anadarko Petroleum Corporation  
Name & Address: P.O. Box 351  
Liberal, KS 67905-0351

Lease Name Interstate Unit Well # 84  
County Morton  
Well Total Depth 4180 135.85 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8.5/8 feet 1166

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Sargent & Horton Plugging, Inc. License Number 31151  
Address Rt. 1, Box 49BA, Tyrone, OK 73951-9731

Company to plug at: Hour: 1 p.m. Day: 28 Month: 6 Year: 19 94

Plugging proposal received from Don Horton  
(company name) Sargent & Horton Plugging, Inc. (phone) 405-854-6575

Perfs: 5 1/2" at 4176' w/150 sx cement, PBSD 4170', Perfs at 4084-92, 4102-08', TOC 3885'.  
1st plug pump 2 sx hulls and 25 sx cement at perfs,  
2nd plug pump 45 sx cement at 1200',  
3rd plug pump 30 sx cement at 700',  
4th plug pump 10 sx cement at 40-0'.

Plugging Proposal Received by Glenn Barlow (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 4:30 p.m. Day: 29 Month: 6 Year: 19 94

ACTUAL PLUGGING REPORT 1st plug pumped 2 sx hulls and 25 sx cement at perfs, TOC 3885',  
2nd plug pumped 45 sx cement at 1200',  
3rd plug pump 30 sx cement at 700',  
4th plug pump 10 sx cement at 40 to -4'.

RECEIVED  
STATE CORPORATION COMMISSION

JUL 08 1994

Remarks: Used common cement by Sargent & Horton. Recovered 1220' of 5 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

I (did / did not) observe this plugging.

7-11-94  
40805  
6-29

Signed Glenn R Barlow (TECHNICIAN)