

15-129-10317-ppp0

1 020355

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- Docket #E-21,363

NW NE NW, SEC. 28, T 34 S, R 43 W/E

4950 feet from S section line

3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4549

Lease Name Interstate Unit Well # 52

Operator: Anadarko Petroleum Corporation

County Morton 136.50

Name & Address P.O. Box 351

Well Total Depth 4200 feet

Liberal, KS 67905-0351

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 1179

Abandoned Oil Well Gas Well Input Well X SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Sargent's Casing Pulling Serv. License Number 6547

Address 620 S. Lincoln, Liberal, KS 67901

Company to plug at: Hour: 2:30 p.m. Day: 14 Month: 2 Year: 19 91

Plugging proposal received from Don Horton

(company name) Sargent's Casing Pulling Serv. (phone) 316-624-7455

were: 5 1/2" at 4199' (TOC 2795'), PBTD 4162', Perfs at 4123-36'

1st plug pump 2 sx hulls and 20 sx cement at perfs,

2nd plug pump 50 sx cement at 1200-1000',

3rd plug pump 25 sx cement at 650-550',

4th plug pump 10 sx cement at 40-0'.

Plugging Proposal Received by Glenn Barlow (TECHNICIAN)

Plugging Operations attended by Agent?: All Part X None

Operations Completed: Hour: 1 p.m. Day: 18 Month: 2 Year: 19 91

ACTUAL PLUGGING REPORT Hole loaded with mud with tubing.

1st plug pumped 2 sx hulls and 20 sx cement at perfs,

2nd plug at 1200', pumped 50 sx cement to 1000',

3rd plug pumped 25 sx cement at 650-550',

4th plug pumped 10 sx cement at 40' to -3'.

RECEIVED
STATE COR. CONSERVATION DIVISION
2-21-91
FFR 21 1001

CONSERVATION DIVISION
WICHITA, KANSAS

Remarks: Used common cement by Sargent's. Recovered 2400' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

(did you) observe this plugging.

Signed Glenn Barlow (TECHNICIAN)

DATE 2-25-91
30873
2-18