

15-129-10555-0000

Drilled 9/25/55

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-
NW/4, SEC. 27, T 34 S, R 43 W/X
1320 feet from NX section line
1325 feet from WG section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4549
Operator: Anadarko Petroleum Corporation
Name:
Address: P.O. Box 351
Liberal, KS 67905-0351

Lease Name Roll Well # 1-27
County Morton
Well Total Depth 3027 - 98.38 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 587

Abandoned Oil Well Gas Well X Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Sargent & Horton Plugging, Inc. License Number 31151
Address Rt. 1, Box 49BA, Tyrone, OK 73951-9731

Company to plug at: Hour: 1 p.m. Day: 18 Month: 1 Year: 1994

Plugging proposal received from Don Horton

(company name) Sargent & Horton Plugging, Inc. (phone) 405-854-6515

were: 5 1/2" at 3027' w/300 sx cement, PBD 2900', Perfs at 2749'-2989' (10 sets)

1st plug pump 1 1/2 sx hulls and 25 sx cement at perfs,

2nd plug pump 30 sx cement at 800', 3rd plug pump 50 sx cement at 610'

4th plug pump 10 sx cement at 40 to -4'.

RECEIVED
STATE CORPORATION COMMISSION
JAN 26 1994
CONSERVATION DIVISION
Wichita, Kansas

Plugging Proposal Received by Glenn Barlow (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 4 p.m. Day: 20 Month: 1 Year: 1994

ACTUAL PLUGGING REPORT 1st plug pumped 1 1/2 sx hulls and 25 sx cement at perfs,

2nd plug pumped 30 sx cement at 800',

3rd plug pumped 50 sx cement at 610',

4th plug pumped 10 sx cement at 40 to -4'.

Remarks: Used common cement by Sargent & Horton Plugging. Recovered 917' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

I (did / did not) observe this plugging.

39837

Signed Glenn R. Barlow (TECHNICIAN)