

1100368

TO:
STATE CORPORATION COMMISSION

API NUMBER 15-129-10,526-0001
NW SEC. 24, T 34 S, R 43 W

CONSERVATION DIVISION - PLUGGING SECTION 1320 FEET FROM NORTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 1270 FEET FROM WEST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME KANSAS WELL # 1-24

TECHNICIAN'S PLUGGING REPORT

COUNTY MORTON

OPERATOR LICENSE # 4549

WELL TOTAL DEPTH 3010 FEET

OPERATOR: ANADARKO PETROLEUM CORP PRODUCTION CSG: SIZE 4 1/2" @ 2965' WITH 100 SX

NAME AND PO BOX 351 SURFACE CASING: SIZE 7" @ 590' WITH 300 SX

ADDRESS LIBERAL, KS 67905-0351

ABANDONED OIL WELL GAS WELL X INPUT WELL SWD WELL D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR SARGENT & HORTON PLUGGING, INC LICENSE NUMBER 31151

ADDRESS RT. 1, BOX 49BA, TYRONE, OK 73951-9731

COMPANY TO PLUG AT: HOUR: 9:30 AM DAY: 23 MONTH: 06 YEAR: 2000

PLUGGING PROPOSAL RECEIVED FROM DON HORTON

(COMPANY NAME) SARGENT & HORTON PLUGGING, INC (PHONE) 580-854-6515

WERE: PERFS AT 2553-2644

1ST PLUG SPOT 20 SX CEMENT AND 200# HULLS AT 2553 TO 2353. 2ND PLUG PULL TO 640' CIRCULATE
HOLE WITH MUD. SPOT 80 SX CEMENT AT 640-240'. 3RD PLUG PULL TO 40' SPOT 10 SX CEMENT.

PLUGGING PROPOSAL RECEIVED BY GARY WITNERS

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE

OPERATIONS COMPLETED: HOUR: 11:30 AM DAY: 23 MONTH: 06 YEAR: 2000

ACTUAL PLUGGING REPORT

1ST PLUG SPOT 20 SX CEMENT AND 200# HULLS AT 2553 TO 2353'. 2ND PLUG PULL TO 640'.
CIRCULATE HOLE WITH MUD. SPOT 80 SX CEMENT AT 640-240'. 3RD PLUG PULL TO 40' SPOT 10 SX
CEMENT.

RECEIVED
ST. CORPORATION COMMISSION

JUL 6 2000

REMARKS: USED COMMON CEMENT BY SARGENTS. RECOVERED 718' OF 4 1/2" CASING.
(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING.

SIGNED

(TECHNICIAN)

FORM CP-2/3