

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-129-20044-00-01

Spot: NESW

Sec/Twnshp/Rge: 23-34S-43W

1980 feet from S Section Line, 3300 feet from E Section Line

Lease/Unit Name: STATE OF KANSAS

Well Number: 2-23

County: MORTON

Total Vertical Depth: 4500 feet

Operator License No.: 4549

Conductor Pipe: Size

feet:

8/46.25

Op Name: ANADARKO PETROLEUM CORPORATION

Surface Casing: Size 8.625

feet: 1179

WITH 350 SX CMT

Address: 17001 NORTHCHASE DRIVE

Production: Size

feet:

HOUSTON, TX 77060

Liner: Size

feet:

Well Type: SWD

UIC Docket No: D16491.0

Date/Time to Plug: 05/17/2002 2:00 PM

Plug Co. License No.: 31151

Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.

Proposal Rcvd. from: DON HORTON

Company: SARGENT AND HORTON PLUGGIN Phone: (580) 854-6515

Proposed  
Plugging  
Method:

LOAD HOLE WITH MUD. SPOT 50 SX CMT AT 875'. SPOT 50 SX CMT AT 325'. SPOT 15 SX CMT AT 0-40'.

Plugging Proposal Received By: SCOTT ALBERG

WitnessType: Plugging Operations 100% Witnessed (Complete)

Date/Time Plugging Completed: 05/20/2002 5:00 PM

KCC Agent: JIM HOLLAND

Actual Plugging Report:

PBTD 1099'. PERFS AT 910-920'. CMT PLUG FROM 1115' TO 1225'. PULL TUBING OUT OF RETAINER AT 886'. LAY DOWN 1 JOINT. 1ST PLUG PUMP 50 SX CMT DOWN 2 3/8" TUBING AT 855'. 2ND PLUG PULL OUT OF HOLE WITH TUBING TO 325'. LOAD HOLE WITH MUD & PUMP 50 SX CMT. GOOD CIRCULATION. ON 05/20/2002: 2ND PLUG PULL OUT OF HOLE TO 40' WITH TUBING. LOAD HOLE & PUMP 10 SX CMT TO SURFACE.

RECEIVED

MAY 29 2002

KCC WICHITA

Remarks: USED COMMON CEMENT BY SARGENTS. NO CASING RECOVERED.

Plugged through: TBG

District: 01

Signed

Jim Holland PRTT  
(TECHNICIAN)

1000000000

5-30-02 MAY 22 2002

2002061857 MP

Form C-23