

2 100382

API NUMBER 15- 191-21,739 - 0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

125' W C E/2, SEC. 9, T 35 S, R 2 W/E
SE NE

3365 feet from N/S section line

455 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5673

Lease Name Weber Well # 2

Operator: W. L. Kirkman, Inc.

County Sumner 161.30

Name & Address P. O. Box 782290

Well Total Depth 4963 PB 4688 feet

Wichita, KS 67278

Conductor Pipe: Size 5-1/2" feet 4923' / 225 SX

316-685-2290

Surface Casing: Size 8-5/8" feet 255' / 200 SX

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated Perf 4302'-06'

Plugging Contractor Kelso Casing Pulling Co. License Number 6050

Address

Company to plug at: Hour: 11:30a Day: 6 Month: 9 Year: 1988

Plugging proposal received from Mike Kelso

(company name) Kelso Casing (phone)

were: Sand 4250' 5 sx cement - shoot & pull pipe - redimix to surface

Plugging Proposal Received by W.K. (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 4:00p Day: 6 Month: 9 Year: 1988

ACTUAL PLUGGING REPORT Sanded to 4250' & dumped 5 sx cement with bailer - gas problem - shot pipe at 3500' - pulled to 1240' and pumped 20 sx of gel - pulled 5-1/2" to 500' and pumped 40 sx of cement - pulled pipe to 300' and circulated 120 ssx to surface - pulled remaining pipe & filled hole with 5 sx of cement.

RECEIVED
STATE CORPORATION COMMISSION
SEP 12 1988
CONSERVATION DIVISION
Wichita, Kansas

Remarks: B.J. Titan #422307 60/40 6% gel

(If additional description is necessary, use BACK of this form.)

INVOICED

(did / did not) observe this plugging.

DATE 9-14-88

Signed Johnny C. Sanders (TECHNICIAN)

WICHITA NO. 2223