

2 050865

15-191-21530-0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-

TECHNICIAN'S PLUGGING REPORT

Operator License # 5673

Lease Name Weber Well # 1

Operator: W. L. Kirkman

County Sumner 152.95

Name & Address P. O. Box 782290

Well Total Depth 4706 feet

Wichita, KS 67218-2290

Conductor Pipe: Size feet

Surface Casing: Size 8-5/8 feet 242

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelso License Number

Address

Company to plug at: Hour: 8:00a Day: 25 Month: 6 Year: 19 89

Plugging proposal received from

(company name) (phone)

were: 5-1/2" set @ 4706' w/175 sx - perf @ 4706-08' - plug @ 4550' & 50' sand

& sx - shoot & pull pipe - 25 sx 60/40 poz 2% gel @ 925' - 300' to surface.

Plugging Proposal Received by (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: Day: 29 Month: 6 Year: 19 89

ACTUAL PLUGGING REPORT Pushed plug to 4550' & dumped 50' sand on plug then 5 sx

cement - shot & pulled 3300' of 5-1/2" casing - spotted 25 sx cement @ 925' -

circ cement 300' to surface 40/60 poz 2% gel.

RECEIVED
STATE CORPORATION COMMISSION
WICHITA, KANSAS

JUL 15 1989
7-13-89
CONSERVATION DIVISION
Wichita, Kansas

Remarks: Allied Cement Co. #1954

(If additional description is necessary, use BACK of this form.)

INVOICED

(did / xxxxxx) observe this plugging.

DATE 7-18-89

Signed Glenn Ward (TECHNICIAN)

INV. NO. 25363 WK