

STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 Finney State Office Building  
 130 South Market, Rm 2078  
 Wichita, Kansas 67202

WELL PLUGGING RECORD  
 K.A.R.-82-3-117

NUMBER 15-189-222750000  
 LEASE NAME HJV JENNISON "A"  
 WELL NUMBER 1  
1250 Ft. from S Section Line  
3730 Ft. from E Section Line  
 SEC. 24 TWP. 34 RGE. 37 ( E ) or ( W )  
 COUNTY STEVENS  
 Date Well Completed 5-21-98  
 Plugging Commenced 10-18-98  
 Plugging Completed 10-18-98

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days

LEASE OPERATOR ANADARKO PETROLEUM CORPORATION  
 ADDRESS P.O. BOX 351, LIBERAL, KS 67901-0351  
 PHONE # ( 316 ) 624-6253 OPERATORS LICENSE NO. 4549

Character of Well D&A  
 (Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on \_\_\_\_\_ (date)  
 by GARY WINTERS (KCC District Agent's Name)

Is AC0-1 filed? YES If not, is well log attached? \_\_\_\_\_

Producing Formation NONE Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 6900

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS				CASING RECORD		
Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8"	1744	NONE
				5-1/2"	6887	2196'

Describe in detail, the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each set. MIRU PL. PMP 3 SKS HULLS & 20 SKS 60/40 POZ CMT W/6% GEL. PERE 4-WAY SHOT AT 3255'. PUMP 60 SKS 60/40 POZ CMT W/ 6% GEL. BACK OFF 5-1/2" CASING AT 2196' W/ STRING SHOT. PULL 5-1/2" CSG TO 1794'. SPOT 50 SKS CMT AT 1794'. TOH TO 600' & SPOT 25SKS AT 600'. TOH TO 43' & SPOT 10SKS CMT FROM 43' TO SURFACE. 9PPG MUD BETWEEN PLUGS. CUT OFF 8-5/8" CSG 3' BELOW GL AND CAP. PERMANENTLY INSCRIBE WELL NAME, NUMBER AND DATE PLUGGED ON CAP.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor HALLIBURTON ENERGY SERVICES License No. 5287  
 Address P. O. BOX 1598, LIBERAL, KANSAS 67905-1598

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: ANADARKO PETROLEUM CORPORATION

STATE OF KANSAS COUNTY OF SEWARD, ss.  
L. MARC HARVEY, DRILLING TECHNICAL ASSISTANT (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) L. Marc Harvey 10-23-98  
 L. MARC HARVEY, DRILLING TECHNICAL ASSISTANT  
 (Address) P.O. BOX 351, LIBERAL, KS 67901-0351

SUBSCRIBED AND SWORN TO before me this 23rd day of October, 1998

Theda L. Shroy  
 Notary Public

My Commission Expires: 5-15-99