

STATE OF KANSAS
STATE CORPORATION COMMISSION
Finney State Office Building
30 South Market, Rm 2078
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-189-22300-0000

LEASE NAME SPANGLER "A"

WELL NUMBER 3H

320 Ft. from S Section Line

320 Ft. from E Section Line

SEC. 18 TWP. 34S RGE 37W(E) or (W)

COUNTY STEVENS

Date Well Completed 11-20-98

Plugging Commenced 4-15-99

Plugging Completed 4-16-99

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days

LEASE OPERATOR ANADARKO PETROLEUM CORPORATION

ADDRESS P.O. BOX 351, LIBERAL, KS 67901-0351

PHONE # (316) 624-6253 OPERATORS LICENSE NO. 4549

Character of Well _____

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 4-2-99 (date)

by GARY WINTERS (KCC District Agent's Name)

Is AC0-1 filed? YES If not, is well log attached? _____

Producing Formation CHASE Depth to Top 2650 Bottom 2894 T.D. 3024

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
CHASE	GAS	2650	2894	8-5/8"	713	0
				5-1/2"	3084	0

Describe in detail, the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set. TOH W/ TGB. MIX & PMP 5 SXS HULLS & 25 SXS CMT. TAG TOP OF CMT @ 2735. MIX & PMP 3 SXS HULLS & 25 SXS CMT. LOAD HOLE W/ 9PPG MUD TO 750. MIX & PMP 80 SXS CMT FROM 750' TO 4'. MIX & PMP 10 SXS CMT DOWN 5-1/2" & 8-5/8" ANNULUS. CUT OFF AND CAP CSG 4' BELOW GL. STATE WITNESS : GAREY WINTERS

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor SARGENT AND HORTON PLUGGING, INC. License No. 31151

Address RT 1 BOX 49BA, TYRONE, OK 73951-9731 PHONE: (580) 854-6515

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: ANADARKO PETROLEUM CORPORATION

STATE OF KANSAS COUNTY OF SEWARD, ss.

SHAWN D. YOUNG, DIVISION PRODUCTION ENGINEER (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Shawn D. Young
SHAWN D. YOUNG, DIVISION PRODUCTION ENGINEER

(Address) P.O. BOX 351, LIBERAL, KS 67901-0351

RECEIVED
STATE CORPORATION COMMISSION

SUBSCRIBED AND SWORN TO before me this 27th day of April, 1999.

APR 28 1999

Shirley J. Childers
Notary Public

CONSERVATION DIVISION
Wichita, Kansas

My Commission Expires: _____

