

15-189-10053-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER N/A

LEASE NAME Cunningham 1-26

WELL NUMBER B-1

3300 Ft. from S Section Line

1983.2 Ft. from E Section Line

SEC. 13 TWP. 34 RGE. 37 (E) or (W)

COUNTY Stevens

Date Well Completed 8/13/67

Plugging Commenced 7/25/85

Plugging Completed 8/1/85

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Mobil Oil Corporation

ADDRESS P. O. Box 5444

PHONE#(303) 298-2696 OPERATORS LICENSE NO. 5208

Character of Well Abandonment

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dodge City

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation 6313-17 6347-51 Depth to Top _____ Bottom _____ T.D. _____

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS Surface 8-5/8 24# set @ 1773 CASING RECORD 4-1/2 9-1/2# set @ 6913 Producing

Formation	Content	From	To	Size	Put in	Pulled out
6313-17 6347-51	CIBP # 6300			4.5		
	52 bbls mud	6280	3059			
	100 sx 3% C/C	3059	2500			
	12 bbls mud	2500	1823			
	1000 sx 50/50 POZ	1823	Surface			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

See attached page.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Patrick Well Service License No. _____

Address Liberal, KS

STATE OF Colorado COUNTY OF Denver, ss.

J. E. Dawson (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Richard Schumard 8/13/85

(Address) P. O. Box 5444, Denver, CO 80217-5444

SUBSCRIBED AND SWORN TO before me this 19th day of August, 19 85

Clara M. [Signature]
Notary Public CORPORATION COMMISSION

My Commission Expires: My Commission expires February 14, 1988

8-23-85
AUG 23 1985

PLUGGING PROCEDURE

- 7/24/85 Moved rig in and rigged up.
- 7/25/85 Pulled 1" tbg string. Pengo ran guage ring to 6300. Ran in CIBP set @ 6300. Ran in dump bailer, spotted cement on top of CIBP, approx. 20'. Ran in csg gun, perforated Hugoton-Council Grove @ 3034 4/SPF. Start in with 75 jts of 2-3/8 tbg. SION.
- 7/26/85 Ran tbg to 6251.20. Halliburton pump in 52 bbls of mud to 3059 at 3 bbls @ min. Pulled tbg out. Halliburton bull headed 100 sx of Class H w/3% CC. Squeezing Hugoton and Council Grove.
- 7/29/85 Pengo ran in csg gun - tagged cement at 2500, perforated csg @ 1834. Ran tbg to 2500 spotted 12 bbls of mud to 1800, pulled tbg. Pumped 525 sx of 50/50 POZ, had no return to surface. SION
- 7/30/85 Pengo ran in temperature log, tagged cement at 1602, temperature log showed cement behind csg at 1500. Perforated @ 1480, started pump cement down backside of csg, pressured up after 290' of 50/50 was pumped in. Ran in another csg gun re-perforated csg @ 1400. Circulated csg and backside with 70 bbls. of fresh water, had good return. Pump 475 sx of 50/50 POZ mix down annulus around backside to surface, had good return.
- 8/1/85 Red Welding Service and F&D Rousabout Service went out and cut off production and surface csg 6' below ground.

RECEIVED
STATE CORPORATION COMMISSION

AUG 23 1985

CONSERVATION DIVISION
Wichita, Kansas