

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

15-189-20006-0000

API NUMBER N/A

LEASE NAME Cunningham Ut. #126

WELL NUMBER #3

SPOT LOCATION 661' FWL 660' FSL

SEC. 13 TWP. 34S RGE. 37 ~~XXX~~ of (W)

COUNTY Stevens

Date Well Completed 8/13/67

Plugging Commenced 10/8/84

Plugging Completed 10/13/84

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Mobil Oil Corporation

ADDRESS P. O. Box 5444, Denver, CO 80231

PHONE # (303) 298-2696 OPERATORS LICENSE NO. 5208

Character of Well Gas  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dodge City

Is ACO-1 filed? Yes If not, is well log attached? --

Producing formation Morrow/St. Louis Depth to top 6350/6722 bottom 6362/6774 T.D. 6914

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Surface				8 5/8"	1775'	None
Production				4 1/2"	6914'	1934'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state the character of same and depth placed, from feet to feet each set. Pumped through production casing 2.5 bbls. 9 ppg - 36 cp mud from 6862' to 6708'. Pumped 10 sax class A cement from 6708'-6590'. Pumped 4.5 bbls. mud from 6590'-6313'. Pumped 10 sax class A cement from 6313'-6197'. Pumped 47 bbls. mud from 6197'-3316'. Pumped 10 sax class A from 3316'-3200'. Pumped 5 bbls. mud from 3200'-3084'. Pumped 10 sax class A cement from 3084'-2900'. Cut production casing at 1900'. Pumped 95 bbls mud through production casing to fill hole to surface. Spotted 50 sax class A cement from (if additional description is necessary, use BACK of this form.) (cont. on back)

Name of Plugging Contractor Midwest Casing Pulling License No. 6497  
Address Box F, Sublette, KS 67877

RECEIVED

STATE OF Kansas COUNTY OF Haskell, ss. STATE CORPORATION COMMISSION

John E. Dawson (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God. DEC 10 1984

CONSERVATION DIVISION  
Wichita, Kansas  
(Signature) Alberta Lopez for J. E. Dawson  
(Address) P. O. Box 5444, Denver, CO 80217

SUBSCRIBED AND SWORN TO before me this 14th day of November, 1984

[Signature]  
Notary Public

My Commission expires: 3-29-88

1825'-1642'. Spotted 10 sax class A from 830'-800'. Poured in 15 sax class A cement at surface from 50' to surface. Cut casing off 5 ft. below surface and welded steel plate over opening.