

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-189-20,646-0000
 LEASE NAME K.U. Endowment "C"
 WELL NUMBER 1
 SPOT LOCATION 2540 FSL & 1250 FEL
 SEC. 35TWP. 34SRGE. 38 (W) or (W)
 COUNTY Stevens
 Date Well Completed 5/30/85
 Plugging Commenced 5/30/85
 Plugging Completed 5/30/85

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Anadarko Production Company
 ADDRESS Box 351, Liberal, Kansas 67901

PHONE # (316) 624-6253 OPERATORS LICENSE NO. 5469

Character of Well D&A
 (Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dodge City

Is ACO-1 filed? Yes If not, Is well log attached? _____

Producing formation NA Depth to top _____ bottom T.D. 3120

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS _____ CASING RECORD _____

Formation	Content	From	To	Size	Put In	Pulled out
Surface	727	0	727	8-5/8	727	0
Production	3119	0	3119	4-1/2	3119	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. Mix 260 sxs 60/40 Pozmix 2% Gel 3% CaCl down 4-1/2 csg from 3098 to GL, Mix and pump 20 sxs 60/40 Pozmix 2% Gel 3% CaCl down annulus PSI to 200#, cut off 8-5/8 three feet below GL & weld on cap.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor None License No. _____
 Address _____

STATE OF Kansas COUNTY OF Seward, ss.

Paul Campbell (employee of operator) or
 (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Paul Campbell
 Paul Campbell, Division Production Manager
 (Address) Box 351, Liberal, Kansas 67901

SUBSCRIBED AND SWORN TO before me this 13th day of June, 19 85

STATE NOTARY PUBLIC
 ELIZABETH J. HOOPER
 Seward County, Kansas
 My Appt. Expires 7-26-87

Elizabeth J. Hooper
 Notary Public

My Commission expires: _____

RECEIVED
 STATE CORPORATION COMMISSION

JUN 14 1985

CONSERVATION DIVISION
 Wichita, Kansas

GABBERT-JONES, INC.
WICHITA, KAS.

- DRILLERS' WELL LOG -

K.U. ENDOWMENT "C" #1
2540' FSL & 1250' FEL Sec. 35-34S-38W
Stevens County, Kansas

COMMENCED: 12/20/82
COMPLETED: 12/31/82

OPERATOR: ANADARKO PRODUCTION COMPANY - Liberal, Kas.

Depth		Formation	Remarks
From	To		
0	740	Sand-Redbed	Ran 18 jts. of 20# 8 5/8" csg. set @ 727' cemented w/500 sax Common 3% CC PD @ 9:00 PM 12/20/82
740	1381	Redbed	
1381	2355	Shale	
2355	2359	Shale-Lime	
2359	3120	Lime-Shale	
	3120	TD	Ran 75 Jts. of 10 1/2# 4 1/2" csg. set @ 3119' cemented w/550 sax. Lite wt. 4% Gel - 150 sx SALT SAT Posmix + .5% CFR 2 PD @ 103:30 AM 12/31/82

STATE OF KANSAS]
]
COUNTY OF SEDGWICK]

I, the undersigned, being duly sworn on oath, state that the above Drillers Well Log is true and correct to the best of my knowledge and belief and according to the records of this office.

GABBERT-JONES, INC.
[Signature]
James S. Sutton, II - President

Subscribed & Sworn to before me
this sixth day of January, 1983.

[Signature]
Lola Lenore Costa - Notary Public

My Commission expires November 21, 1984.

RECEIVED
STATE CORPORATION COMMISSION
MAR 15 1985
CONSERVATION DIVISION
Wichita, Kansas



GABBERT-JONES, INC.
WICHITA, KAS.

- DRILLERS' WELL LOG -

K.U. ENDOWMENT "C" #1
2540' FSL & 1250' FEL Sec. 35-34S-38W
Stevens County, Kansas

COMMENCED: 12/20/82
COMPLETED: 12/31/82

OPERATOR: ANADARKO PRODUCTION COMPANY - Liberal, Kas.

Depth		Formation	Remarks
From	To		
0	740	Sand-Redbed	Ran 18 jts. of 20# 8 5/8" csg. set @ 727' cemented w/500 sax Common 3% CC PD @ 9:00 PM 12/20/82
740	1381	Redbed	
1381	2355	Shale	
2355	2359	Shale-Lime	
2359	3120	Lime-Shale	
	3120	TD	Ran 75 Jts. of 10 1/2# 4 1/2" csg. set @ 3119' cemented w/550 sax. Lite wt. 4% Gel - 150 sx SALT SAT Posmix + .5% CFR 2 PD @ 103:30 AM 12/31/82

STATE OF KANSAS]
]
COUNTY OF SEDGWICK]

I, the undersigned, being duly sworn on oath, state that the above Drillers Well Log is true and correct to the best of my knowledge and belief and according to the records of this office.

GABBERT-JONES, INC.
[Signature]
James S. Sutton, II - President

Subscribed & Sworn to before me
this sixth day of January, 1983.

[Signature]
Lola Lenore Costa - Notary Public

My Commission expires November 21, 1984.

