

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-189-20,647-0000

LEASE NAME Beavers "B"

WELL NUMBER I

SPOT LOCATION 2540'FSL & 1250'FEL

SEC. 34TWP. 34RGE. 38()or(W)

COUNTY Seward

Date Well Completed 5/30/85

Plugging Commenced 5/30/85

Plugging Completed 5/30/85

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Anadarko Production Company

ADDRESS Box 351, Liberal, Kansas 67901

PHONE # (316) 624-6253 OPERATORS LICENSE NO. 5469

Character of Well D & A
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dodge City, Kansas

Is ACO-1 filed? Yes, Attached If not, Is well log attached? _____

Producing formation Council Grove Depth to top 2995 bottom 3038 T.D. 3115

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Surface	723	-0-	723	8 5/8"	723	-0-
Production	3115	-0-	3115	4 1/2"	3115	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Mix & Pump 260 sxs 60/40 Pozmix 2% Gel 3% C&C down 4 1/2" csg 3032' to 0'. Pmp 50 sxs. Pozmix 2% Gel & 3% C&C Down Annulus. Cut csg off 3' below GI & Weld Cap on 8 5/8 csg.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor None License No. _____
Address _____

RECEIVED

STATE CORPORATION COMMISSION

STATE OF Kansas COUNTY OF Seward, ss.

Paul Campbell, Division Production Manager (employee of operator) of JUN 14 1985

(operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Paul Campbell
(Address) Box 351, Liberal, Kansas 67901

SUBSCRIBED AND SWORN TO before me this June day of June, 19 85



Notary Public

My Commission expires: _____

Form CP-4 1-84
Revised 06-83

- DRILLERS WELL LOG -

GABBERT-JONES, INC.
WICHITA, KAS.

BEAVERS "B" #1
2540' FSL & 1250' FEL
Sec. 34-34S-38W
Stevens County, Kas.

COMMENCED: 1/1/83
COMPLETED: 1/6/83

OPERATOR: ANADARKO PRODUCTION COMPANY - Liberal, Kas.

Depth		Formation	Remarks
From	To		
0	415	Sand-Redbed	
415	730	Redbed	Ran 18 jts. of 20# 8 5/8" csg.
730	973	Sand-Redbed-Anhydrite	set @ 722' cemented w/550 sax
973	1346	Redbed-Anhydrite	Common 3% CC - PD @ 11:00 PM
1346	1680	Sand-Shale	1/1/83
1680	2020	Sand-Anhydrite-Shale	
2020	2272	Sand-Shale	
2272	2370	Shale	Ran 73 jts. of 10 1/2# 4 1/2" csg.
2370	2745	Shale-Lime	set @ 3118' cemented w/500 sax
2745	2890	Lime-Shale	Lite wate - 4% Gel + 150 sax
2890	3015	Lime	Salt Sat Posmix .5% CFR 2
3015	3115	Lime-Shale	PD @ 8:15 PM 1/6/83
	3115'	TD	

STATE OF KANSAS]
]
COUNTY OF SEDGWICK]


I, the undersigned, being duly sworn on oath, state that the above Drillers Well Log is true and correct to the best of my knowledge and belief and according to the records of this office.

GABBERT-JONES, INC.
[Signature]
James S. Sutton, II - Pres.

Subscribed & Sworn to before me
this 14th day of January, 1983.

[Signature]
Lola Lenore Costa - Notary Public

My Commission expires November 21, 1984.



- DRILLERS WELL LOG -

GABBERT-JONES, INC.
WICHITA, KAS.

BEAVERS "B" #1
2540' FSL & 1250' FEL
Sec. 34-34S-38W
Stevens County, Kas.

COMMENCED: 1/1/83
COMPLETED: 1/6/83

OPERATOR: ANADARKO PRODUCTION COMPANY - Liberal, Kas.

Depth		Formation	Remarks
From	To		
0	415	Sand-Redbed	
415	730	Redbed	Ran 18 jts. of 20# 8 5/8" csg.
730	973	Sand-Redbed-Anhydrite	set @ 722' cemented w/550 sax
973	1346	Redbed-Anhydrite	Common 3% CC - PD @ 11:00 PM
1346	1680	Sand-Shale	1/1/83
1680	2020	Sand-Anhydrite-Shale	
2020	2272	Sand-Shale	
2272	2370	Shale	Ran 73 jts. of 10 1/2# 4 1/2" csg.
2370	2745	Shale-Lime	set @ 3118' cemented w/500 sax
2745	2890	Lime-Shale	Lite wate - 4% Gel + 150 sax
2890	3015	Lime	Salt Sat Posmix .5% CFR 2
3015	3115	Lime-Shale	PD @ 8:15 PM 1/6/83
	3115'	TD	

STATE OF KANSAS]
]
COUNTY OF SEDGWICK]

RECEIVED
STATE CORPORATION COMMISSION
MAR 15 1985
CONSERVATION DIVISION
Wichita, Kansas

I, the undersigned, being duly sworn on oath, state that the above Drillers Well Log is true and correct to the best of my knowledge and belief and according to the records of this office.

GABBERT-JONES, INC.
[Signature]
James S. Sutton, II - Pres.

Subscribed & Sworn to before me
this 14th day of January, 1983.

[Signature]
Ibla Lenore Costa - Notary Public

My Commission expires November 21, 1984.

