

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-129-21213-00-01
Spot: N2SE Sec/Twnshp/Rge: 19-34S-41W
1980 feet from S Section Line, 1320 feet from E Section Line
Lease/Unit Name: SLEETH A Well Number: 2H
County: MORTON Total Vertical Depth: 2180 feet

Operator License No.: 4549

Conductor Pipe: Size

feet:

\$70.85

Op Name: ANADARKO PETROLEUM CORPORATIO

Surface Casing: Size 8.625

feet: 667

Address: 17001 NORTHCHASE DRIVE
HOUSTON, TX 77060

Production: Size 5.5

feet: 2180

Liner: Size

feet:

Well Type: GAS

UIC Docket No:

Date/Time to Plug: 05/10/2002 2:00 PM

Plug Co. License No.: 31151

Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.

Proposal Rcvd. from: DON HORTON

Company: SARGENT AND HORTON PLUGGIN Phone: (580) 854-6515

Proposed
Plugging
Method:

CIBP SET AT 2070'. Dump 2 sx on cibp. Dump 30 sx cmt from 1450'-1200'. Displace with 9 ppg mud. Dump 70 sx cmt from 600' to surface. Cut off casing 3' below G.L. Restore Location

Plugging Proposal Received By: RICHARD LACEY

Witness Type: Plugging Operations Were Not Witnessed

Date/Time Plugging Completed: 05/10/2002 5:00 PM

KCC Agent: RICHARD LACEY

Actual Plugging Report:

PBTD 2070'. PERFS AT 1975-1982'. CIBP @ 2070'. DUMP 2 SX HULLS & 25 SX CMT ON CIBP. 1ST PLUG AT 1450-1200' WITH 30 SX CMT. DISPLACE WITH MUD. 2ND PLUG AT 600' TO 0' WITH 70 SX CMT. PUMPED 15 SX CMT DOWN 5 1/2" X 8 5/8" ANNULUS. PRESSURED TO 500#.

RECEIVED

MAY 20 2002

KCC WICHITA

Remarks: USED COMMON CEMENT BY SARGENTS. NO CASING RECOVERED.

Plugged through: CSG

District: 01

Signed

Richard M. Lacey

(TECHNICIAN)

MAY 13 2002

521-02

20020618/18