

To: 1 020641  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-129-00029-0000  
15- Completion date 11/16/56

C SE 7, SEC. 7, T 34 S, R 41 W/X  
1320 feet from S section line  
1320 feet from E section line

TECHNICIAN'S PLUGGING REPORT  
Operator License # 4549  
Operator: Anadarko Petroleum Corp.  
Name & Address P.O. Box 351  
Liberal, KS 67905-0351

Lease Name Wacker Well # 1-7  
County Morton  
Well Total Depth 5298 172.18 feet  
Conductor Pipe: Size            feet  
Surface Casing: Size 8 5/8 feet 1465

Abandoned Oil Well            Gas Well   X   Input Well            SWD Well            D&A             
Other well as hereinafter indicated           

Plugging Contractor Sargent and Horton Plugging, Inc. License Number 31151  
Address Rt. 1, Box 49BA, Tyrone, OK 73951-9731

Company to plug at: Hour: 4 p.m. Day: 22 Month: 2 Year: 19 93

Plugging proposal received from Don Horton  
(company name) Sargent & Horton Plugging, Inc. (phone) 405-854-6515

were: 5 1/2" at 4533' w/800 sx cement, PBTD 3150', 3770', 3310', 3240', 3180',  
Perfs at 3017-25, 3041-45, 3054-64, 3108-12, 3118-22'

1st plug pump 2 1/2 sx hulls and 50 sx cement at perfs through packer, release, load hole with mud,  
2nd plug spot 30 sx cement at cut off, 3rd plug spot 50 sx cement at 1500',  
4th plug spot 30 sx cement at 700', 5th plug spot 10 sx cement at 35 to -4'.

Plugging Proposal Received by Glenn Barlow  
(TECHNICIAN)

Plugging Operations attended by Agent?: All   X   Part            None           

Operations Completed: Hour: 5 p.m. Day: 25 Month: 2 Year: 19 93

ACTUAL PLUGGING REPORT 1st plug pumped 2 1/2 sx hulls and 50 sx cement at perfs through packer,  
released, and loaded hole with mud,

2nd plug spotted 50 sx cement at 1500',  
3rd plug spotted 30 sx cement at 700',  
4th plug spotted 10 sx cement at 35 to -4'.

RECEIVED  
TE CORPORATION COMMISSION  
MAR 1 1993

All plugs displaced with mud. CONSERVATION DIVISION  
Wichita, Kansas

Remarks: Used common cement by Sargent & Horton. Recovered 1914' of 5 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

I (did / ~~xxxxxxx~~) observe this plugging.

Signed Glenn R Barlow  
(TECHNICIAN)

27451