

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
209 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

7-19

API NUMBER 15-  
175-20,367-00-01

C NE NE, SEC. 5, T 34 S, R 41 W/EX  
4620 feet from S section line  
660 feet from E section line

Lease Name Cherokee "C" Well # 1  
County Morton 178.75  
Well Total Depth 5500 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 1418

TECHNICIAN'S PLUGGING REPORT

Operator License # 4549  
Operator: Anadarko Petroleum Corporation  
Name & Address P.O. Box 351  
Liberal, KS 67905-0351

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Sargent & Horton Plugging, Inc. License Number 31151  
Address Rt. 1, Box 49BA, Tyrone, OK 73951-9731

Company to plug at: Hour: 8 a.m. Day: 18 Month: 7 Year: 1995

Plugging proposal received from Don Horton

(company name) Sargent & Horton Plugging, Inc. (phone) 405-854-6515

were: 4 1/2" at 5499' w/400 sx cement, PBDT 5404', Perfs at 5138-50, 5184-94'

1st plug pump 2 sx hulls and 20 sx cement at perfs,

2nd plug pump 25 sx cement at 3000',

3rd plug pump 50 sx cement at 1450',

4th plug pump 40 sx cement at 650', 5th plug pump 10 sx cement at 40 to -4'.

RECEIVED  
STATE CORPORATION COMMISSION

JUL 27 1995

CONSERVATION DIVISION  
WICHITA, KANSAS

Plugging Proposal Received by Glenn Barlow  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part  None \_\_\_\_\_

Operations Completed: Hour: 4 p.m. Day: 19 Month: 7 Year: 19 95

ACTUAL PLUGGING REPORT 1st plug pumped 2 sx hulls and 20 sx cement at perfs,

2nd plug pumped 25 sx cement at 3000',

3rd plug pumped 50 sx cement at 1450',

4th plug pumped 40 sx cement at 650',

5th plug pumped 10 sx cement at 40 to -4'.

Remarks: Used common cement by Sargent & Horton. Recovered 3014' of 4 1/2" casing.

(if additional description is necessary, use BACK of this form.)

DATE AUG 02 1995  
GATE 43224  
US'S NO. 43224

Signed Glenn R. Barlow  
(TECHNICIAN)