

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-129-00331-00-00
Spot: CSWNE Sec/Twnshp/Rge: 27-33S-41W
1980 feet from N Section Line, 1987 feet from E Section Line
Lease/Unit Name: BARKER Well Number: 1-27
County: MORTON Total Vertical Depth: 2280 feet

Operator License No.: 4549 Conductor Pipe: Size _____ feet: _____
Op Name: ANADARKO PETROLEUM CORPORATION Surface Casing: Size 7 feet: 449 *\$ 74.10*
Address: 17001 NORTHCHASE DRIVE Production: Size 5.5 feet: 2274
HOUSTON, TX 77060 Liner: Size _____ feet: _____

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 11/13/2001 9:00 AM
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.
Proposal Rcvd. from: DON HORTON Company: SARGENT AND HORTON PLUGGIN Phone: (580) 854-6515

Proposed Plugging Method: PUMP 100# HULLS & 55 SX CMT. 1ST PLUG AT 600' WITH 30 SX CMT. 2ND PLUG PUMP 5 SX CMT TO 64'. PUMP 20 SX CMT DOWN BACKSIDE. PRESSURE CHECK.

Plugging Proposal Received By: JIM HOLLAND Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 11/14/2001 11:30 AM KCC Agent: JIM HOLLAND

Actual Plugging Report:

PBTD 2186'. PERFS AT 2130-2178'. CMT RETAINER @ 2184'. OPERATOR HAD BOND LOG THAT INDICATED THAT TOP OF CEMENT ON 5 1/2" WAS AT 325'. RUN IN HOLE WITH TUBING TO TOP OF FISH @ 1870'. PUMP 100# HULLS & 55 SX CMT FOR BOTTOM PLUG. GOOD CIRCULATION. PULL OUT OF HOLE WITH TUBING TO 600'. LOAD HOLE. PUMP 30 SX PLUG FROM 600' TO 200'. GOOD CIRCULATION. PULL OUT OF HOLE WITH TUBING TO 64'. PUMP TOP PLUG TO SURFACE WITH 5 SX CMT. HOOK ONTO BACKSIDE & PUMP 20 SX CMT. NO PRESSURE. WAIT 4 HOURS. PUMP 20 SX CMT DOWN BACKSIDE AND FILLED TO TOP WITH CMT. FELL AWAY. SDON. 11/14/01: PUMPED 5 SX CMT. FILLED BACKSIDE TO SURFACE.

Remarks: USED COMMON CEMENT BY SARGENTS. NO CASING RECOVERED.

Plugged through: TBG

District: 01

Signed

Jim Holland PART II
(TECHNICIAN)

RECEIVED

NOV 21 2001

KCC WICHITA

NOV 19 2001

11-26-01

2002060969

Form CR-23