

1090967

TO: STATE CORPORATION COMMISSION

11-2

API NUMBER 15-129-00333 ~~6000~~  
C NW SE SEC. 33 T 33 S, R 41 W

CONSERVATION DIVISION - PLUGGING SECTION 1980 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 1980 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME BAKER WELL # 1-33

TECHNICIAN'S PLUGGING REPORT

COUNTY MORTON 73.45

OPERATOR LICENSE # 4549

WELL TOTAL DEPTH 2260 FEET

OPERATOR: ANADARKO PETROLEUM CORP PRODUCTION CSG: SIZE 4 1/2" @ 2253' WITH 250 SX

NAME AND PO BOX 351 SURFACE CASING: SIZE 8 5/8" @ 645' WITH 350 SX

ADDRESS LIBERAL, KS 67905-0351

ABANDONED OIL WELL GAS WELL X INPUT WELL SWD WELL D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR SARGENT & HORTON PLUGGING INC LICENSE NUMBER 31151

ADDRESS RT 1, BOX 49BA, TYRONE, OK 73951-9731

COMPANY TO PLUG AT: HOUR: 9:00 AM DAY: 02 MONTH: 11 YEAR: 1998

PLUGGING PROPOSAL RECEIVED FROM DON HORTON

(COMPANY NAME) SARGENT & HORTON PLUGGING INC (PHONE) 405-854-6515

WERE: PERFS AT 2074-2149

1ST PLUG PUMP 25 SX CEMENT AND 300# HULLS TO BOTTOM. LOAD HOLE WITH MUD.

2ND PLUG SPOT 50 SX CEMENT AT 670'. PULL TO 40' FILL WITH CEMENT.

PLUGGING PROPOSAL RECEIVED BY STEVE MIDDLETON

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL PART NONE X

OPERATIONS COMPLETED: HOUR: 4:45 PM DAY: 02 MONTH: 11 YEAR: 1998

ACTUAL PLUGGING REPORT 11-16-98

1ST PLUG PUMP 25 SX CEMENT AND 300# HULLS ON BOTTOM.. LOAD HOLE WITH MUD.

2ND PLUG SPOT 50 SX CEMENT AT 670'. PULL TO 40'. FILL WITH CEMENT.

REMARKS: USED COMMON CEMENT BY SARGENTS. RECOVERED 714' OF 4 1/2" CASING.

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID NOT) OBSERVE THIS PLUGGING.

SIGNED [Signature] (TECHNICIAN) FORM CP-2/3

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 16 1998

11-23-98  
60356

R [Signature]