

To: 1 020638  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 129-20,074-~~0000~~ 123  
C SW NW, SEC. 17, T. 33 S, R. 40 W XX

TECHNICIAN'S PLUGGING REPORT

Operator License # 4549  
Operator: Anadarko Petroleum Corporation  
Name:  
Address P.O. Box 351  
Liberal, KS 67905-0351

3300 feet from S section line  
4620 feet from E section line  
Lease Name Low "C" Well # 4  
County Morton 187.00  
Well Total Depth 5754 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 1495

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Sargent's Casing Pulling License Number 6547  
Address P.O. Box 506, Liberal, KS 67905-0506

Company to plug at: Hour: 3 p.m. Day: 7 Month: 1 Year: 19 93  
Plugging proposal received from Don Horton

(company name) Sargent's Casing Pulling (phone) 316-624-7455  
were: 5 1/2" at 5753' w/150 sx cement, PBTD 5745', Perfs 5388-5460', 5692-97', 120' of 13 3/8"

1st plug pump 2 sx hulls and 25 sx cement,  
2nd plug pull casing, run tubing to 2200' and pump hole full of mud, displace 30 sx cement at 2200',  
3rd plug pump 50 sx cement at 1530', 4th plug pump 35 sx cement at 700', 5th plug pump 10  
sx cement at 40 to -4'. Plugging Proposal Received by Glenn Barlow  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_  
Operations Completed: Hour: 4 p.m. Day: 13 Month: 1 Year: 19 93

ACTUAL PLUGGING REPORT 1st plug pumped 2 sx hulls and 25 sx cement, packer in hole at 5680',  
2nd plug pulled casing, ran tubing to 2200' and pumped hole full of mud, displaced 30 sx cement  
at 2200',  
3rd plug pumped 50 sx cement at 1530',  
4th plug pumped 35 sx cement at 700',  
5th plug pumped 10 sx cement at 40 to -4'.

Remarks: Used common cement by Sargent's. Recovered 2200' of 5 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

I (did / ~~XXXXXX~~) observe this plugging.

Signed Glenn P. Barlow  
(TECHNICIAN)

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 19 1993  
CONSERVATION DIVISION  
WICHITA, KANSAS

37338