

15-129-20075-0000

To: 1051224  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- Drill Completion Date 3/23/72  
S/2 SE. SEC. 18, T. 33 S, R. 40 W/4E

TECHNICIAN'S PLUGGING REPORT

Operator License # 3316

1980 460 feet from S section line

1320 feet from E section line

Operator: Matagorda Island Exploration Corp.  
Name & Address: P.O. Box 351  
Liberal, KS 67905-0351

Lease Name Low "D" Well # 4

County Morton 187.20

Well Total Depth 5760 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 1478

Abandoned Oil Well X Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Halliburton License Number

Address

Company to plug at: Hour: 9 a.m. Day: 24 Month: 10 Year: 19 89

Plugging proposal received from Marvin Johnson

(company name) Matagorda Island Exploration Corporation (phone) 316-697-2188

were: 4 1/2" at 5759' PBD 5731' Perfs at 5684-5690' 2 3/8" tubing stuck to 712'

1st plug at 5648' with 25 sx cement, 2nd plug at 1488' with 25 sx cement,

3rd plug at 700' with 20 sx cement,

4th plug at 40' with 5' sx cement,

5th plug pump 200 sx cement down 8 5/8" X 4 1/2" annulus.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 3:30 p.m. Day: 24 Month: 10 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug pumped 30 sx cement down 2 3/8" tubing to 5648', 2nd plug

Perforated 2 3/8" tubing at 1528-1428', pumped 25 sx cement,

3rd plug pumped 20 sx cement at 712-610',

4th plug pumped 15 sx cement at 50-0',

5th plug pumped 200 sx cement down 8 5/8" X 4 1/2" annulus.

11-1-89 NOV - 1 1989

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Halliburton. Recoverd 712' of 2 3/8" tubing.

(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 11-2-89

INV. NO. 26311

10-24

Signed Richard W. Lacey (TECHNICIAN)