

To: 1 020477
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 129-20,542-0000 182
C NW NE, SEC. 19, T. 33 S, R. 40 W/E

TECHNICIAN'S PLUGGING REPORT

Operator License # 4549
Operator: Anadarko Petroleum Corporation
Name & Address: P.O. Box 351
Liberal, KS 67905-0351

4620 feet from S section line
1980 feet from E section line
Lease Name Low "B" Well # 2
County Morton
Well Total Depth 5810 188.82 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 1485

Abandoned Oil Well _____ Gas Well X Input Well _____ SWD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor Sargent's Casing Pulling Service License Number 6547
Address 620 S. Lincoln, Liberal, KS 67901

Company to plug at: Hour: 10 a.m. Day: 16 Month: 7 Year: 19 92

Plugging proposal received from Don Horton

(company name) Sargent's Casing Pulling Service (phone) 316-624-7455

were: 4 1/2" at 5809' w/300 sx cement, PBTD 5795', Perfs at 5404-20, 5466-74, 5738-42'

1st plug pump 2 sx hulls and 20 sx cement at perfs.

2nd plug pump 75 sx cement at 1535',

3rd plug pump 50 sx cement at 750',

4th plug pump 15 sx cement at 40-0',

Plugging Proposal Received by Glenn Barlow
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 3 p.m. Day: 20 Month: 7 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug pumped 2 sx hulls and 20 sx cement at perfs.

2nd plug pumped 75 sx cement at 1535',

3rd plug pumped 50 sx cement at 750',

4th plug pumped 15 sx cement at 40-0'.

Heavy mud between all plugs.

Remarks: Used common cement by Sargent's. Recovered 4212' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

I (did / ~~did not~~) observe this plugging.

8-6-92
35867
7-20

Signed Glenn R. Barlow
(TECHNICIAN)

RECEIVED
STATE CORPORATION COMMISSION
JUL 22 1992
CONSERVATION DIVISION
WICHITA, KANSAS