

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-129-21398-00-00
Spot: W2SW Sec/Twnshp/Rge: 20-33S-40W
2610 feet from S Section Line, 1320 feet from W Section Line
Lease/Unit Name: DAVISON A Well Number: 3
County: MORTON Total Vertical Depth: 5900 feet

Operator License No.: 4549 Conductor Pipe: Size _____ feet:
Op Name: ANADARKO PETROLEUM CORPORATION Surface Casing: Size 8.625 feet: 1535 WITH 470 SX CMT
Address: 1201 LAKE ROBBINS DRIVE Production: Size 5.5 feet: 5888 WITH 240 SX CMT
THE WOODLANDS, TX 77380 Liner: Size _____ feet:

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 10/09/2002 2:00 PM
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.
Proposal Rcvd. from: JUSTIN RAITHEL Company: ANADARKO PETROLEUM Phone: (852) 601-3130


Proposed Plugging Method: PUMP 25 SX CMT & 200# HULLS. 1ST PLUG AT 2700' WITH 30 SX CMT. 2ND PLUG AT 1575' WITH 50 SX CMT. 3RD PLUG AT 600' WITH 40 SX CMT. 4TH PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: JIM HOLLAND Witness Type: Plugging Operations Partially Witnessed
Date/Time Plugging Completed: 10/10/2002 1:00 PM KCC Agent: STEVE MIDDLETON

Actual Plugging Report:
PBTD 5730'. PERFS AT 5620-32'. PUMP 25 SX CMT & 200# HULLS OVER PERFS. 1ST PLUG LOAD HOLE WITH MUD. PUMP 30 SX CMT AT 2700'. 2ND PLUG PULL TO 1575' & PUMP 50 SX CMT. 3RD PLUG PULL TO 600' & SPOT 40 SX CMT. 4TH PLUG PULL TO 40' & PUMP 10 SX CMT TO SURFACE. STAYED FULL.

RECEIVED
OCT 17 2002
KCC WICHITA

Remarks: USED COMMON CEMENT BY SARGENTS. RECOVERED 2741' OF 5 1/2" CASING.
Plugged through: CSG

District: 01 Signed:  (TECHNICIAN)
OCT 14 2002
10-18-02
2003060655
Form 10-273