

To: STATE CORPORATION COMMISSION
Wichita State Office Bldg. PLUGGING SECTION NE NE SW SE, SEC. 26, T 33 S, R 40 W/EX
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15- 129-21,385-0000
1280 feet from S section line
1350 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 4549
Operator: Anadarko Petroleum Corporation
Name
Address P.O. Box 351
Liberal, KS 67905-0351

Lease Name Stout F Well # 2
County Morton 199.88
Well Total Depth 6150 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 1668

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ O&A
Other well as hereinafter indicated _____

Plugging Contractor Sargent & Horton Plugging, Inc. License Number 31151
Address Rt. 1, Box 49BA, Tyrone, OK 73951-9731

Company to plug at: Hour: 10 a.m. Day: 28 Month: 11 Year: 1995

Plugging proposal received from Don Horton
(company name) Sargent & Horton Plugging, Inc. (phone) 405-854-6515

core: 5 1/2" at 5715' w/250 sx cement, PBTD 5667', Perfs at 5400-44, 5340-60'
1st plug pump 200 lbs. hulls and 25 sx cement, displace to 5090',
2nd plug pump 35 sx cement at cut off,
3rd plug pump 35 sx cement at 1700',
4th plug pump 35 sx cement at 600', 5th plug pump 10 sx cement at 40'.

Plugging Proposal Received by Duane Rankin (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____
Operations Completed: Hour: 4 p.m. Day: 28 Month: 11 Year: 1995

RECEIVED
STATE CORPORATION COMMISSION
Year: 1995
12-7-95
WICHITA, KANSAS

ACTUAL PLUGGING REPORT 1st plug at 5340-5240' with 300 lbs. hulls and 25 sx cement
2nd plug at 2612' with 35 sx cement,
3rd plug at 1700-1618' with 35 sx cement,
4th plug at 600' with 35 sx cement,
5th plug at 40-0' with 10 sx cement.

Remarks: Used common cement by Sargent & Horton. Recovered 2640' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

(did / XXXXXXX) observe this plugging.
Signed Gary Wenter (TECHNICIAN)

12-8-95
44279