

To: 1
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 129-20,777 - 0000
C NW NW, SEC. 27, 'T' 33 S, R 40 W

TECHNICIAN'S PLUGGING REPORT

Operator License # 4549

Operator: Anadarko Petroleum Corporation
Name &
Address P. O. Box 351
Liberal, KS 67901

4620 feet from S section line

4620 feet from E section line

Lease Name Mangeles "B" Well # 1

County Morton 201.83

Well Total Depth 6210 St. Louise feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 1649

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Johnson Drilling Company License Number 7860

Address 111 Main, Evansville, Ind. 47708

Company to plug at: Hour: 2:00 pm Day: 17 Month: November Year: 1985

Plugging proposal received from John Hannah

(company name) Anadarko (phone) 316-624-6253

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 3303
10 sx cement Plugging Proposal Received by Richard W. Lacey Anhydrite N/A
(TECHNICIAN)

1st plug at 2800' with 50 sx cement

2nd plug 30' below the base of the surface pipe with 50 sx cement

3rd plug at 750' with 40 sx cement
solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rat hole with 10 sx cement, 7th plug to circulate mouse hole with
10 sx cement

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 4:30 pm Day: 17 Month: November Year: 19 85

ACTUAL PLUGGING REPORT 1st plug at 2800' with 50 sx cement, 2nd plug at 1680' with 50

sx cement, 3rd plug at 750' with 40 sx cement, 4th & 5th plugs - solid bridge - hulls -

plug at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rat hole with

10 sx cement, 7th plug to circulate mouse hole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton.
(If additional description is necessary, use BACK of this form.)

INVOICED
DATE NOV 25 1985
INV. NO. 11193

RECEIVED
STATE CORPORATION COMMISSION
Signed Richard W. Lacey
(TECHNICIAN)
NOV 20 1985