

To: 1
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-119-20,722-0000

SE-SE-NE SEC. 30, T 33 S, R 27 W1/2

2970 feet from S section line

330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License 8060

Lease Name Hauer Well 1-30

Operator Name Zinke & Zumbo, Ltd.

County Meade 202.96

Address 111 W. 5th Suite 220

Well Total Depth 6245 Lower Meade feet

Tulsa, Okla.

Conductor Pipe: Size _____ feet

74103

Surface Casing: Size 8 5/8 feet 1529

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A

Other well as hereinafter indicated _____

Plugging Contractor Damac Drilling, Inc License Number 6333

Address Great Bend Kansas, Box 1164, 625 S. Washington 67530

Company to plug at: Hour: 7:00 AM Day: 10 Month: November Year: 1985

Plugging proposal received from Galen Roberts

(company name) Damac Drilling Inc. Mobile (phone) 316-862-5988

were: 1st plug if in arduable 50' plug w/ 40 sbp cent.

2nd plug base of anhydrite w/ 50 sbp cent.

3rd plug @ 600' w/ 50 sbp cent.

4th plug @ 40' on SB wood plug w/ 10 sbp cent. filling hole to 0'

5th plug circ. 15 sbp cent in rat hole. 6th plug circ. 10 sbp cent in rat

hole. Use 60/40 w/ 6.75 gall Plugging Proposal Received by Paul A. Luthin (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 10:45 AM Day: 10 Month: November Year: 1985

ACTUAL PLUGGING REPORT 1st plug @ 1550' w/ 50 sbp cent. (anhydrite base 1520')

2nd plug @ 600' w/ 50 sbp cent.

3rd plug @ 40' on solid bridge plug w/ 10 sbp cent filling hole to 0'

4th plug circulated 15 sbp cent. in rat hole. 5th plug circulated 10 sbp

cent. in mouse hole.

Halliburton pumped 60/40 w/ 6.75 gall through drill pipe w/

Remarks: hole full of heavy mud.

(If additional description is necessary, use BACK of this form.)

NOTICE: () and () observe STATE CORPORATION COMMISSION's plugging.

DATE 12-9-85

NOV 14 1985

Signed Paul A. Luthin (TECHNICIAN)

DIV. NO. 11351

CONSERVATION DIVISION
Wichita, Kansas
11-10 DEC 15 1985

CARD MUST BE TYPED

State of Kansas
NOTICE OF INTENTION TO DRILL
(see rules on reverse side)

CARD MUST BE SIGNED

Starting Date: October 15, 1985
month day year

API Number 15- 119-20,722-0000
SE SE NE Sec. 30 Twp. 33 S. Rge. 27 East West

OPERATOR: License # 8060
Name Zinke & Trumbo, Ltd.
Address 111 W. 3th., Suite 220
City/State/Zip Tulsa, Okla. 74103
Contact Person Ron F. Crowell
Phone 918-592-5096

2970' Ft North from Southeast Corner of Section
330' Ft West from Southeast Corner of Section
(Note: Locate well on Section Plat on reverse side)

CONTRACTOR: License # 6333
Name Damac Drilling, Inc.
City/State Great Bend, Ks. 67530

Nearest lease or unit boundary line 330 feet.
County Meade
Lease Name Harder Well# 1-30

Well Drilled For: Well Class: Type Equipment:
 Oil Swd Infield Mud Rotary
 Gas Inj Pool Ext. Air Rotary
 DWWO Expl Wildcat Cable

Domestic well within 330 feet: yes no
Municipal well within one mile: yes no

If OWWO: old well info as follows:
Operator _____
Well Name _____
Comp Date _____ Old Total Depth _____
Projected Total Depth 6400 feet
Projected Formation at TD St. Louis
Expected Producing Formations Lansing/KC, Marm., Morrow, St. Louis

Depth to Bottom of fresh water 200 feet
Lowest usable water formation _____
Depth to Bottom of usable water 250 feet
Surface pipe by Alternate: 1 2
Surface pipe to be set 1500 feet
Conductor pipe if any required 60 feet
Ground surface elevation _____ feet MSL

I certify that we will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to K.C.C. specifications.

This Authorization Expires 2-19-86
Approved By RFC 8-19-86

Date 8/15/85 Signature of Operator or Agent Ron F. Crowell Title Production Manager Form C-1 4/84

Moved in 10-26-85 set 15' 19' 0" / 8 3/8"

PUSHER Galen Roberts
TD C249 FORMATION Lower Chester
SURFACE PIPE 8 3/8" @ 1529
ANHYDRITE 1520 ELEVATION NA
STARTING TIME & DATE _____
COMPLETION TIME & DATE 10:45 am 11/10/85
1st PLUG @ 1550 FT. W/ 50 SX
2nd PLUG @ 600 FT. W/ 50 SX
3rd PLUG @ 540 FT. W/ 10 SX
4th PLUG @ _____ FT. W/ _____ SX
HOLES AT HOLE CIRCULATION W/ 15 SX
HOUSE HOLE CIRCULATION W/ 10 SX
WATER SUPPLY WELL PLUGGED W/ _____ SX

TECHNICIAN Halliburton
Anchor - 40' deep
Base w/ 5-0
600' w/ 5-0
40-0-10
air 15' w/ 4 1/2" in. hose
6' of 40 w/ 6 3/4 gell

NOV 14 1985