

DEC 15 1988

To: 1 061175
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-189-20,590-0000

SE SW NW, SEC. 1, T 34 S, R 37 W/E

2970 feet from S section line

4030 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5208

Lease Name Showalter Well # 2

Operator: Mobil Oil Corporation

County Stevens 106.11

Name & Address Box 5444

Well Total Depth 3265 feet

Denver, CO 80217

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 703

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Borderline Inc. License Number 7840

Address RR 3, Box 1043, Ulysses, KS 67878

Company to plug at: Hour: 9 a.m. Day: 15 Month: 12 Year: 19 88

Plugging proposal received from Tony Romerez

(company name) Mobil Oil Corporation (phone) 303-298-2000

were: 5 1/2" at 3180' Perfs at 2987-3037'

1st plug pump 20 barrels mud and CIBP at 2900' with 2 sx cement on top,

2nd plug pump 26 barrels of 50/50 Pozmix cement at 1930',

3rd plug pump 58' sx light cement at 775'.

Plugging Proposal Received by Paul Luthi
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 10:30 a.m. Day: 15 Month: 12 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug pumped 20 barrels mud and CIBP at 2900' with 2 sx
cement on top, plugged through tubing,

2nd plug pumped 26' sx 50/50 Pozmix at 1930',

3rd plug pumped 58' sx light cement at 775'.

CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 50/50 Pozmix and light cement by Halliburton. No casing recovery.
(If additional description is necessary, use BACK of this form.)

1 N.O.L.E.D.
XXXXXX observe this plugging.

DATE DEC 22 1988

Signed Paul A. Luthi
(TECHNICIAN)

INV. NO. 23437