

1100297

6-8

TO: STATE CORPORATION COMMISSION

API NUMBER 15-189-20,166-0000
C SE NE SEC. 36, T 34 S, R 36 W

CONSERVATION DIVISION - PLUGGING SECTION 3300 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 660 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202 LEASE NAME ROEHR WELL # 1-36

TECHNICIAN'S PLUGGING REPORT COUNTY STEVENS 214.99

OPERATOR LICENSE # 5134 WELL TOTAL DEPTH 6615 FEET

OPERATOR: GRAHAM-MICHAELIS CORP. PRODUCTION CSG: SIZE 4 1/2" @ 6614' WITH 150 SX

NAME AND PO BOX 247 SURFACE CASING: SIZE 8 5/8" @ 1698' WITH 800 SX

ADDRESS WICHITA, KS 67201

ABANDONED OIL WELL GAS WELL X INPUT WELL SWD WELL D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR SARGENT & HORTON PLUGGING, INC LICENSE NUMBER 31151

ADDRESS RT. 1, BOX 49BA, TYRONE, OK 73951-9731

COMPANY TO PLUG AT: HOUR: 9:00 AM DAY: 04 MONTH: 06 YEAR: 1999

PLUGGING PROPOSAL RECEIVED FROM DON HORTON

(COMPANY NAME) SARGENT & HORTON PLUGGING, INC (PHONE) 580-854-6515

WERE: PERFS AT 6276-94 (6-10-99)

1ST PLUG PUMP 20 SX CEMENT AND 100# HULLS DOWN TUBING. 2ND PLUG AT 3000' WITH 100 SX

CEMENT. 3RD PLUG AT 1700' WITH 50 SX CEMENT. 4TH PLUG AT 700' WITH 40 SX CEMENT.

5TH PLUG AT 40' WITH 10 SX CEMENT.

RECEIVED
KANSAS
CORPORATION
JUN 10 1999
2:12

PLUGGING PROPOSAL RECEIVED BY RICHARD LACEY

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL PART X NONE

OPERATIONS COMPLETED: HOUR: 4:30 PM DAY: 08 MONTH: 06 YEAR: 1999

ACTUAL PLUGGING REPORT

1ST PLUG SPOT 20 SX CEMENT PLUG WITH 200# HULLS AHEAD AT 6276'.

2ND PLUG SPOT 50 SX CEMENT PLUG AT 2400'.

3RD PLUG SPOT 50 SX CEMENT PLUG AT 1700'.

4TH PLUG SPOT 40 SX CEMENT PLUG AT 700'.

5TH PLUG SPOT 10 SX CEMENT PLUG AT 40' TO SURFACE.

REMARKS: USED COMMON CEMENT BY SARGENTS. RECOVERED 2431' OF 4 1/2" CASING.

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING.

DATE 6-21-99

SIGNED Gary Wentz (TECHNICIAN) FORM CP-2/3

INV. NO. 61098