

To: 1 1977 2-9
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

15-189-20003-0000
API NUMBER 15- Drilled 2/17/67
C SE SE, SEC. 36, T 34 S, R 36 WEX
660 feet from S section line
660 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 32114
Operator: Rosel Fluid Service Inc.
Name & Address: P.O. Box 557
Liberal, KS 67905-0557

Lease Name Roehr Well # 1-36
County Stevens 215.64
Well Total Depth 6635 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 9 5/8 feet 719

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Sargent & Horton Plugging, Inc. License Number 31151
Address Route 1, Box 49BA, Tyrone, OK 73951-9731

Company to plug at: Hour: 8 a.m. Day: 6 Month: 2 Year: 19 98

Plugging proposal received from Don Horton
(company name) Sargent & Horton Plugging, Inc. (phone) 405-854-6515

logs: 7" at 6631' w/425 sx cement, Perfs at 6550-60, 6286-96, 5285-90, CIBP at 3200'
PBSD 6595'

1st plug spot 50 sx cement at 2800', 2nd plug spot 50 sx cement from 740-640',
3rd plug spot 25 sx cement at 390', 4th plug at 40' with 10 sx cement.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 3:15 p.m. Day: 9 Month: 2 Year: 1998

ACTUAL PLUGGING REPORT 1st plug spot 50 sx cement and 4 sx hulls at 2800'. Tagged
plug with wireline at 2443',

2nd plug spotted 50 sx cement at 750'; displaced with mud, RECEIVED
3rd plug pulled casing to 390', spotted 40 sx cement, displaced with mud, STATE CORP
4th plug at 30-0' with 10 sx cement. FEB 18 1998

CONSERVATION DIVISION

Remarks: Used common cement by Sargent & Horton. Recovered 1523' of 7" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED

(did / observe this plugging.

DATE FEB 22 1998

Signed Steve Durrant (TECHNICIAN)

INV. NO. 50117
2-9