

To: 1 100-16
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15- 189-21,492 - 0000
App. SE SW NW SW SEC. 28, T. 34 S, R. 36 W/E
1420 feet from S section line
4700 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License / 30421
Operator: N.L.S. Inc.
Name & Address: P.O. Box 1417
Liberal, KS 67905-1417

Lease Name Parker Well / 1-28
County Stevens
Well Total Depth 6700 217.75 feet
Conductor Pipe: Size 20" feet 40
Surface Casing: Size 8 5/8" feet 1759

Abandoned Oil Well _____ Gas Well Input Well _____ SMO Well _____ O&A _____
Other well as hereinafter indicated _____

Plugging Contractor Sargent's Casing Pulling Service License Number 6547
Address P.O. Box 506, Liberal, KS 67905-0506

Company to plug at: Hour: 1:30 p.m. Day: 17 Month: 5 Year: 1996

Plugging proposal received from Kirby Lillard
(company name) Sargent's Casing Pulling Service (phone) 316-624-7455

Work: 4 1/2" at 6640' w/470 sx cement, PBTD 6480', Perfs at 6293-6310'
1st plug pump 2 sx hulls and 20 sx cement on bottom.
2nd plug at 1200' with 40 sx cement,
3rd plug at 600' with 40 sx cement,
4th plug at 40' with 10 sx cement.

RECEIVED
MAY 28 1996
AS CORP COMM

5-28-96

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 4 p.m. Day: 17 Month: 5 Year: 1996

ACTUAL PLUGGING REPORT 1st plug displaced 2 sx hulls and 20 sx cement to 6200',
2nd plug spotted 40 sx cement at 1020',
3rd plug spotted 40 sx cement at 600',
4th plug spotted 10 sx cement at 40-0'.

Remarks: Used common cement by Sargent's. Recovered 1020' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

1 (did not) observe this plugging.

DATE: JUL 17 1996

INV. NO. 45778

5-17 JUL 17 1996

Signed: Gary Winters (TECHNICIAN)