

1 020287

306 R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 189-21,372 - 0000

S/2 SW, SEC. 25, T 34 S, R 36 W/E
660 feet from S section line
3960 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3988

Lease Name Morris Well # 1-25

Operator: Slawson Exploration Company
Name & Address: 20 North Broadway, Suite 700
Oklahoma City, OK 73102

County Stevens 221.10
Well Total Depth 6803 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 1624

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Sargent's Casing Pulling Service License Number 6547

Address P.O. Box 506, Liberal, KS 67905-0506

Company to plug at: Hour: 4 p.m. Day: 23 Month: 1 Year: 19 90

Plugging proposal received from Doug Blair

(company name) Sargent's (phone) 316-624-7455

were: 4 1/2" at 6626' PBD 6581' Perfs at 6501-04' DV'd at 3432' TOC 2662'

1st plug pump 1 sx hulls and 20 sx cement at perfs, displaced with heavy mud,

2nd plug pump 50 sx cement at 1650',

3rd plug pump 40 sx cement at 650',

4th plug pump 10 sx cement at 40-4'.

Plugging Proposal Received by Glenn Barlow (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part None _____

Operations Completed: Hour: 3:30 p.m. Day: 25 Month: 1 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug pumped 1 sx hulls and 20 sx cement at perfs, displaced with heavy mud,

2nd plug pumped 50 sx cement at 1650',

3rd plug pumped 40 sx cement at 650',

4th plug pumped 10 sx cement at 40-4'.

Heavy mud between all plugs.

RECEIVED
STATE CORPORATION COMMISSION
JAN 30 1990
CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used common cement by Sargent's. Recovered 2632' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.

Signed Glenn R. Barlow (TECHNICIAN)

DATE FEB 07 1990

NOV. NO. 27360
1-25