

To: 1 27777
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-189-21,414, ~~0000~~

NE NW, SEC. 22, T 34 S, R 36 W XX

4620 feet from S section line

3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4782

Lease Name Wells Well # 1-22

Operator: Ensign Operating Co.

County Stevens 221.00

Name: 621 17th St., Ste. 1800

Well Total Depth 6800 feet

Address: Denver, CO 80293

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 1787

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Sargent & Horton Plugging, Inc. License Number 31151

Address Rt. 1, Box 49BA, Tyrone, OK 73951-9731

Company to plug at: Hour: 2:30 p.m. Day: 12 Month: 10 Year: 19 93

Plugging proposal received from Don Horton

(company name) Sargent & Horton Plugging, Inc. (phone) 405-854-6515

ware: 4 1/2" at 6788' w/350 sx cement, PBD 6742', Perfs at 6458-66, 6474-84, 6231-98'

1st plug pump 2 sx hulls and 20 sx cement at perfs, displace with mud,

2nd plug pump 50 sx cement at 3200',

3rd plug pump 50 sx cement at 1520', 4th plug pump 40 sx cement at 700',

5th plug pump 10 sx cement at 40 to -4'.

Plugging Proposal Received by Glenn Barlow (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part None _____

Operations Completed: Hour: 11 a.m. Day: 14 Month: 10 Year: 19 93

ACTUAL PLUGGING REPORT 1st plug pumped 2 sx hulls and 20 sx cement at perfs. Displaced with mud,

2nd plug pumped 50 sx cement at 3200',

3rd plug pumped 50 sx cement at 1520',

4th plug pumped 40 sx cement at 700',

5th plug pumped 10 sx cement at 40 to -4'. All plugs displaced with mud.

Remarks: Used common cement by Sargent & Horton. Recovered 3633' of 4 1/2" casing.

(if additional description is necessary, use BACK of this form) observe this plugging.

10-28-93

39064

Signed Glenn R. Barlow (TECHNICIAN)

RECEIVED
STATE CORPORATION COMMISSION
OCT 20 1993
CONSERVATION DIVISION
Wichita, Kansas