

To: 1 110036
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- Completed 1945
Center, SEC. 2, T 34 S, R 36 (W) X
2640 feet from S section line
2640 feet from E section line
Lease Name Lewis Unit Well # 1
County Stevens 92.76
Well Total Depth 2854 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 10 3/4 feet 711

TECHNICIAN'S PLUGGING REPORT

Operator License # 5208
Operator: Mobil Oil Corporation
Name & Address: P. O. Box 5444
Denver, CO 80217

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Mobil Oil Corporation License Number 5208

Address P. O. Box 5444, Denver, CO 80217

Company to plug at: Hour: 9:30 am Day: 29 Month: May Year: 19 86

Plugging proposal received from Tom Romero

(company name) Mobil (phone) 303-298-2696

were: 7" at 2649' Circulated to surface, 5 1/2" at 2636' Open Hole
1st plug Load hole with mud and spot cement from TD to 2636'

2nd plug fill with mud to 750' and displace 50 sx plug (100' plug)

3rd plug mud to 60' below the surface pipe (55' cement plug)

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 1:00 pm Day: 30 Month: May Year: 19 86

ACTUAL PLUGGING REPORT Pumped 100 bbl salt water (to kill well). Pumped (through casing) 30 bbls 9 lb 36 Vis. mud. Pumped 100 sx Class H 2% Bentonite. Dropped wiper plug and pumped 60 bbls mud. Plug went to 2634' (top of liner). Pumped 20 bbls mud (mud to 658') Sat until 5-30-86. Tagged plug at 2634' and displaced 10 sx 50/50 Pozmix (through tubing). Pulled joints out at 775' and displaced 165 sx cement circulated to surface. Pulled 25 joints tubing and filled pipe full.

Remarks: Cemented by Halliburton.
(If additional description is necessary, use BACK of this form.)
observe this plugging.

STATE CORPORATION COMMISSION

JUN 16 1986

CONSERVATION DIVISION
Wichita, Kansas

Signed James Durrant (TECHNICIAN)

INVOICED

DATE JUN 18 1986

INV. NO. 5-30