

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-189-00609-00-00
Spot: CSW Sec/Twnshp/Rge: 30-34S-37W
1320 feet from S Section Line, 1320 feet from W Section Line
Lease/Unit Name: HARRISON Well Number: 1
County: STEVENS Total Vertical Depth: 2878 feet

Operator License No.: 5208
Op Name: EXXONMOBIL OIL CORP
Address: PO BOX 4358
HOUSTON, TX 77210

Liner 1 Size: 2878 feet: 2401 UNKNOWN
Production Casing Size: 8.625 feet: 2416 UNKNOWN
Surface Casing Size: 12.25 feet: 756 UNKNOWN

93.54

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 04/15/2003 1:00 PM
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.
Proposal Rcvd. from: DON HORTON Company: SARGENT AND HORTON PLUGGI Phone: (580) 854-6515

Proposed Plugging Method: CIBP @ 2380' & 5 SX CMT. PLUG AT 1750' WITH 40 SX CMT. PLUG AT 700' WITH 100 SX CMT. PLUG AT 40' WITH 25 SX CMT.

Plugging Proposal Received By: RICHARD LACEY WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 04/16/2003 11:00 AM KCC Agent: JIM HOLLAND

Actual Plugging Report:


PBTD 2878'. FLUID LEVEL AT 2600' WITH WIRELINE. SET CIBP @ 2380' WITH 5 SX CMT ON TOP. 1ST PLUG RUN IN HOLE WITH WIRELINE & FLOAT. LOAD HOLE WITH MUD TO 1750' & PUMP 40 SX CMT. SDON. 04/16/03: PULL OUT OF HOLE WITH 8 5/8" CASING. 2ND PLUG RUN IN HOLE WITH TUBING TO 760'. LOAD HOLE WITH MUD & PUMP 100 SX CMT. GOOD CIRCULATION. 3RD PLUG PULL OUT OF HOLE TO 40'. LOAD HOLE & PUMP 25 SX CMT TO SURFACE.

RECEIVED
MAY 02 2003
KCC WICHITA

Remarks: USED COMMON CEMENT BY SARGENTS. RECOVERED 760' OF 8 5/8" CASING.

Plugged through: TBG

District: 01



Signed

Jim Holland PART II
(TECHNICIAN)

(TECHNICIAN)

INVESTIGATED

5-5-03

2003061490

