

To: 1
STATE CORPORATION COMMISSION
Wichita State Office Bldg. PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15- 189-22,004 - 0000
App. E/2
NW SW, SEC. 29, T 34 S, R 37 W/E
2000 feet from S section line
4280 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5363

Operator: BEREXCO INC.
Name & Address 970 Fourth Financial Ctr.
Wichita, KS 67202

Lease Name Sturdy Well # 1-29
County Stevens 223.47
Well Total Depth 6876 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 1694'

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor BEREDCO INC. License Number 5147

Address 401 E. Douglas, Wichita, KS 67202

Company to plug at: Hour: _____ Day: _____ Month: _____ Year: 19 _____

Plugging proposal received from Kenny

(company name) BEREDCO INC. (phone) 316-265-2856

Work: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 3200' with 100 sx cement, 2nd plug at 1720' with 50 sx cement,

3rd plug at 850' with 50 sx cement, 4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement,

6th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Bill Johnson
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 6:45 a.m. Day: 4 Month: 11 Year: 19 95

ACTUAL PLUGGING REPORT 1st plug at 3250' with 100 sx cement,

2nd plug at 1720' with 50 sx cement,

3rd plug at 850' with 50 sx cement,

4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement,

6th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton.

(If additional description is necessary, use BACK of this form.)

I (XXX / did not) observe this plugging.

11-16-95

44038

11-4

Signed [Signature]
(TECHNICIAN)

RECEIVED
STATE CORPORATION COMMISSION
NOV 14 1995
INFORMATION DIVISION
WICHITA, KANSAS

FOR KCC USE

FORM C-1 7/91

EFFECTIVE DATE: 10-21-95

State of Kansas 15-189-22,004-0000

FORM MUST BE TYPED
FORM MUST BE SICKED
ALL BLANKS MUST BE FILLED

DISTRICT # 1
GAS? Yes No

NOTICE OF INTENTION TO DRILL
Must be approved by the K.C.C. five (5) days prior to commencing well

Expected Spud Date 10/16/95
Approx. C NW SW Sec 29 Twp 34 S. Rg 37 East West

OPERATOR: License # 5363
Name: BEREXCO INC
Address: 970 Fourth Financial Center
City/State/Zip: Wichita, KS 67202
Contact Person: Evan Mayhev
Phone: (316) 265-3311

2000 feet from South / ~~3155~~ line of Section
4280 feet from East / ~~3155~~ line of Section
IS SECTION REGULAR IRREGULAR?
(NOTE: Locate well on the Section Plat on Reverse Side)
County: STEVENS
Lease Name: STURDY Well #: 1-29
Field Name: WILDCAT

TRACTOR: License #: 5147
Name: BEREDCO INC

* Is this a Prorated/Spaced Field? yes no
Target Formation(s): MORROW - CHESTER
Nearest Lease or unit boundary: 775'
Ground Surface Elevation: 3155 feet MSL
Water well within one-quarter mile: yes no
Public water supply well within one mile: yes no
Depth to bottom of fresh water: 530' 550'
Depth to bottom of usable water: 660' 500'
Surface Pipe by Alternate: 1 2
Length of Surface Pipe Planned to be set: 1500
Length of Conductor pipe required: _____
Projected Total Depth: 6850
Formation at Total Depth: ST. LOUIS
Water Source for Drilling Operations: _____
... well ... farm pond other

Well Drilled For: Well Class: Type Equipment:
 Oil ... Enh Rec ... Infield Mud Rotary
 Gas ... Storage ... Pool Ext. ... Air Rotary
 OUVO ... Disposal Wildcat ... Cable
 Seismic; ... # of Holes ... Other
 Other
OUVO: old well information as follows:
Operator: _____
Well Name: _____
Comp. Date: _____ Old Total Depth _____

Sectional, Deviated or Horizontal wellbore? yes no
yes, true vertical depth: _____
Bottom Hole Location: _____

DNR Permit #: APPLIED FOR
Will Cores Be Taken? yes no
If yes, proposed zone: 620' Alt. I Reg

* PRORATED IN CHASE AND COUNCIL GROVE. AFFIDAVIT Exp. 4/16/96

RECEIVED
KANSAS CORPORATION COMMISSION

004
Pusher Kennedy
SPUD DATE 10-21-95 INIT. SM
LENGTH SURFACE PLANNED _____
RESERVE PIT STATUS- REMOVE FLUID LINED
after salt sect. bbls. when done bbls.
RATHOLED AHEAD? Y N SIZE HOLE
SURFACE PIPE 8 1/2" @ lead CONDUCTOR
ANHYDRITE T- B- ELEVATION
TD 6876 FORMATION St Louis (Moo)
RAN PIPE @ DV TOOL ALT II DONE
@ SX Ft. W/ SX N
Arbuckle Plug @ Ft. W/ SX
Hug./Council @ 3250 Ft. W/ 100 SX
Anhydrite Base @ 1700 Ft. W/ 50 SX
1/2 Base Anyh. @ 850 Ft. W/ 50 SX
1/2, 1/2 Plug @ Ft. W/ SX
Bottom Surface @ Ft. W/ SX
40' Plug @ 40 Ft. W/ 10 SX
RAT HOLE CIRC/W 15 SX MOUSE HOLE W/ 10 SX
WATER WELL 15 SX Wire Well Pond
TECHNICIAN NGV DATE 10/14/95 Hauling
TYPE OF CEMENT 600/4000s mix 6% Cel
STARTING TIME _____ DATE _____
COMPLETION TIME 6:45 (AM/PM) DATE 11/14/95
CEMENT COMPANY HALLIBURTON

RECEIVED
KANSAS CORPORATION COMMISSION
DATE 10/14/95