

1100253

TO: STATE CORPORATION COMMISSION

10-19

API NUMBER 15-189-22,275-~~6000~~
NW NW SE SW SEC. 24, T 34 S, R 37 W

CONSERVATION DIVISION - PLUGGING SECTION 1250 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 1550 FEET FROM WEST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME HJV JENNISON "A" WELL # 1

TECHNICIAN'S PLUGGING REPORT

COUNTY STEVENS 224.25

OPERATOR LICENSE # 4549

WELL TOTAL DEPTH 6900 FEET

OPERATOR: ANADARKO PETROLEUM CORP. PRODUCTION CSG: SIZE 5 1/2" @ 6887' WITH 160 SX

NAME AND PO BOX 351 SURFACE CASING: SIZE 8 5/8" @ 1744' WITH 360 SX

ADDRESS LIBERAL, KS 67905-0351

ABANDONED OIL WELL GAS WELL INPUT WELL SWD WELL D/A X

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR HALLIBURTON ENERGY SERVICES LICENSE NUMBER 5287

ADDRESS 1100 WEST PANCAKE, LIBERAL, KS 67901

COMPANY TO PLUG AT: HOUR: 8:00 AM DAY: 19 MONTH: 10 YEAR: 1998

PLUGGING PROPOSAL RECEIVED FROM JACK TUMAN

(COMPANY NAME) HALLIBURTON (PHONE) 316-624-3879

WERE: PERFS AT 6798-6802, 6764-6772, 6370-84, 5260-5188, 5309-5310 SQUEEZED

1ST PLUG SET CIBP AT 6500', 6370'-6384' & 6300'. PUMP 20 SX CEMENT WITH 300# HULLS AT 5188'.

PERFORATE AT 3255' & CEMENT WITH 60 SX. 2ND PLUG AT 1794' WITH 50 SX CEMENT.

3RD PLUG AT 600' WITH 25 SX CEMENT.

4TH PLUG AT 40'-0' WITH 10 SX CEMENT.

PLUGGING PROPOSAL RECEIVED BY GARY WINTERS

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL PART X NONE

OPERATIONS COMPLETED: HOUR: 5:00 PM DAY: 19 MONTH: 10 YEAR: 1998

ACTUAL PLUGGING REPORT

1ST PLUG SET CIBP AT 6500', 6370'-6384', & 6300'. PUMP 20 SX CEMENT WITH 300# HULLS AT

5188'. PERFORATE AT 3255' AND CEMENT WITH 60 SX. 2ND PLUG AT 1794' WITH 50 SX CEMENT.

3RD PLUG AT 600' WITH 25 SX CEMENT. 11-5-98

4TH PLUG AT 40'-0' WITH 10 SX CEMENT.

REMARKS: 60/40 POZMIX 6% GEL BY HALLIBURTON. RECOVERED 2200' OF 5 1/2" CASING.
BACK OFF 5 1/2" CASING AT 2200'

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING.

SIGNED Gary Winters (TECHNICIAN) FORM CP-2/3

11-6-99 60270

10-19

JAN 30 1999