

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-129-20,542-

LEASE NAME Low "B"

WELL NUMBER 2

4620 Ft. from S Section Line

1980 Ft. from E Section Line

SEC. 19 TWP. 33 SRGE. 40 (S) or (W)

COUNTY Morton

Date Well Completed 1-7-82

Plugging Commenced 7-16-92

Plugging Completed 7-20-92

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Anadarko Petroleum Corporation

ADDRESS P.O. Box 351, Liberal, Kansas 67905-0351

PHONE# (316) 624-6253 OPERATORS LICENSE NO. 4549

Character of Well Gas

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 7-15-92 (date)

by Glenn Barlow (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? -

Producing Formation Morrow Depth to Top 5404 Bottom 5420 T.D. 5810

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	1485	0
				4 1/2	5809	4212

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from    feet to    feet each set. Circ hole w/mud. Pmp 2 sxs hulls + 20 sxs cmt @ 5404-5304. Pull free point. Shoot 4 1/2 csg @ 4212. Pmp 75 sxs cmt @ 1535-1385. Pmp 50 sxs cmt @ 750-650. Pmp 15 sxs cmt @ 50-3. Cut off 8 5/8 csg 3' below ground level & cap. Rec 4212' 4 1/2 csg. KCC witnessed. Restore location.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sargent's Casing Pulling Service License No.   

Address 620 S. Lincoln, Liberal, Kansas 67901

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Anadarko Petroleum Corporation

STATE OF Kansas COUNTY OF Seward, ss.

Beverly J. Williams, Engineering Technician (Employee of Operator, or Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Beverly J. Williams

(Address) P.O. Box 351, Liberal, KS 67905-0351

SUBSCRIBED AND SWORN TO before me this 25th day of August, 19 92

C Cheryl Steers  
Notary Public

My Commission Expires:   

