

STATE OF KANSAS
STATE CORPORATION COMMISSION
Finney State Office Building
30 South Market, Rm 2078
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-129-21398-00-00
API NUMBER 1512921398

LEASE NAME DAVISON

WELL NUMBER A-3

2610 Ft. from S Section Line

3960 Ft. from E Section Line

SEC. 20 TWP. 33 RGE 40 (E) or (W)

COUNTY MORTON

Date Well Completed 11-28-1995

Plugging Commenced 10-09-2002

Plugging Completed 10-11-2002 (date)

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days

LEASE OPERATOR ANADARKO PETROLEUM CORPORATION

ADDRESS 701 S TAYLOR, STE 400 AMARILLO, TX 79101

PHONE # (806) 457-4600 OPERATORS LICENSE NO. RECEIVED

Character of Well GAS

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

NOV 12 2002
KCC WICHITA

The plugging proposal was approved on 10-3-2002 (date)

by RICHARD LACEY (KCC District Agent's Name).

Is AC0-1 filed? YES If not, is well log attached? _____

Producing Formation KEYS Depth to Top 5620 Bottom 5632 T.D. 5900

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
KEYS	GAS	5620	5632	8-5/8	1535	0
				5-1/2	5888	2741

Describe in detail, the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set. PLUG PERES WITH 25 SXS CMT AND 3 SXS HULLS FROM 5620 TO 5620. SHOOT 5-1/2 CSG OFF T 2741. SPOT 30 SXS CMT 2700 TO 2600. SPOT 50 SXS CMT FROM 1585 TO 1435. SPOT 40 SXS CMT FROM 550 TO 430. SPOT 10 SXS FROM 40 TO 3. CUT OFF AND CAP 8-5/8 CSG 3 BELOW GL.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor SARGENT AND HORTON PLUGGING, INC. License No. 31151

Address RT 1 BOX 498A, TYRONE, OK 73951-9731 PHONE: (580) 854-6515

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: ANADARKO PETROLEUM CORPORATION

STATE OF TEXAS COUNTY OF POTTER, ss.

CRAIG R. WALTERS, P.E., DIVISION PRODUCTION ENGINEER (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Craig R. Walters
CRAIG R. WALTERS, P.E., DIV. PROD. ENGINEER

(Address) 701 S. TAYLOR, STE 400 AMARILLO, TX 79101



SUBSCRIBED AND SWORN TO before me this 6 day of November, 2002

Lori Pearson
Notary Public

My Commission Expires: 2/26/05

OR