

STATE OF KANSAS
STATE CORPORATION COMMISSION
Finney State Office Building
130 South Market, Rm 2078
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-129-21385 - 0000

LEASE NAME STOUT "F"

WELL NUMBER 2

1280 Ft. from S Section Line

1350 Ft. from E Section Line

SEC. 26 TWP. 33 RGE 40 (X) or (W)

COUNTY MORTON

Date Well Completed 7-19-95

Plugging Commenced 11-27-95

LEASE OPERATOR ANADARKO PETROLEUM CORPORATION

ADDRESS P.O. BOX 351, LIBERAL, KS 67901-0351

PHONE # (316) 624-6253 OPERATORS LICENSE NO. 4549

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

RECEIVED Plugging Completed 11-28-95
STATE CORPORATION COMMISSION (date)

The plugging proposal was approved on 11-24-95

by GARY WINTERS DEC - 6 1995 (KCC District Agent's Name)

Is AC0-1 filed? YES If not, is well log attached? 12-6-95

Producing Formation NONE Depth to Top Wichita Kansas Bottom Bottom T.D. 6150

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| Formation | Content | From | To | Size | Put In | Pulled Out |
|-----------|---------|------|----|--------|--------|------------|
| | | | | 8-5/8" | 1668' | NONE |
| | | | | 5-1/2" | 5715' | 2612' |
| | | | | | | |
| | | | | | | |

Describe in detail, the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
MIRU PUMP TRUCK & CSG PULLERS, PMP 35 SXS HULLS & 25 SXS CMT DWN CSG FROM 5340-5140 FEET. PULL FREE POINT ON 5-1/2" AND CUT OFF AT 2612 FEET. SPOT 60 SXS CMT FROM 2600-2500 FEET. PULL 5-1/2" TO 1700 FEET. SPOT 35 SXS CMT FROM 1700-1600 FEET. PULL 5-1/2" TO 600 FEET. SPOT 35 SXS FROM 600-500 FEET. PULL 5-1/2" TO 40 FEET. SPOT 10 SXS FROM 40-0 FEET. CUT 8 5/8" OFF 3 FEET BELOW GL. CAP & PERMANENTLY INSCRIBE WELL NAME AND DATE PLUGGED ON CAP. RDMO CASING PULLERS. RESTORE LOCATION. WITNESSED BY KCC REP GARY WINTERS.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor: SARGENT & HORTON PLUGGING License No. 31151

Address RT. 1, BOX 49BA, TYRONE, OKLAHOMA 73951-9731

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: ANADARKO PETROLEUM CORPORATION

STATE OF KANSAS COUNTY OF SEWARD, ss.

DAVID W. KAPPLE (Employee of Operator) or (xxxxxxx) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) David W. Kapple

(Address) P.O. BOX 351, LIBERAL, KS 67901-0351

SUBSCRIBED AND SWORN TO before me this 4th day of December, 1995

My Commission Expires: _____



Freda L. Hinz
Notary Public