

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-189-20590 - 0000

LEASE NAME Schowalter #1 Unit

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 2

2970 Ft. from S Section Line

4030 Ft. from E Section Line

SEC. 01 TWP. 34S RGE. 37W (E) or (W)

COUNTY Stevens

LEASE OPERATOR Mobil Oil Corporation

ADDRESS P.O. Box 5444, Denver, CO. 80217

PHONE (303) 298-2069 OPERATORS LICENSE NO. 5208

Date Well Completed 9-8-82

Character of Well Gas

Plugging Commenced 12-14-88

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 12-15-88

The plugging proposal was approved on November 1, 1988 (date)

by Paul Luthy, Dodge City (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation Council Grove Depth to Top 2997' Bottom 3037' T.D. 3165'

Show depth and thickness of all water, oil and gas formations.

RECEIVED
STATE CORPORATION COMMISSION

OIL, GAS OR WATER RECORDS | CASING RECORD 1-3-89
JAN - 3 1989

Formation	Content	From	To	Size	Put in	Pulled out
Council Grove	Gas, Water	0	703'	8-5/8"	703'	
		0	3165'	5-1/2"	3165'	

CONSERVATION DIVISION
Wichita, Kansas

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

20 bbls 9# 36 vis mud @ 3126'-2900', CIBP @ 2900' set with 2 sx cmt @ 2900'-2872'
24 bbls 9# 36 vis mud @ 2972'-1934', 26 sx 50/50 poz @ 1934'-1690',
23 bbls 9# 36 vis mud @ 1690'-780', 70 sx Halliburton Light @ 780'-0

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Halliburton License No. 5287

Address P.O. Box 1598, Liberal, KS 67901

STATE OF Kansas COUNTY OF Seward, ss.

B.R. Maynard, Regulatory Compliance Mgr. (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) B.R. Maynard

(Address) P.O. Box 5444, Denver, CO 80217

SUBSCRIBED AND SWORN TO before me this 29th day of December, 19 88

Joyce George
Notary Public

My Commission Expires: 1/3/91



WELL 15-189-20590-0000

LOCATION _____

PRESENT COMPLETION

DATUM ELEVATION _____

G. L. ELEVATION _____

SURFACE CASING

Size & Wt. 8 5/8 24#

Set at 703 feet

with 275 Sx.

PRODUCTION CASING

Size & Wt. 5 1/2 14#

Grade K55

Condition _____

Set at 3180 feet

with 650 Sx. *Circulated to surface.*

*Circulated 70 Sx
Holliburton Light
to pit*

*22.5 bbls
9# 36 U.S. Mud*

*50/50 B2M + 1755
26 Sx Stone Corrol. 1755*

24 bbls of 9# 36 U.S. Mud

2997

3095

2872 ±

C1BP @ 2900

*20 bbls of 9# 36 U.S. Mud
Connecting Rods*

F. H. P @ 3126

P870 @ 3115

RECEIVED
STATE CORPORATION COMMISSION

JAN - 3 1989

CONSERVATION DIVISION
Wichita, Kansas