

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Rosel Energy, Inc

ADDRESS 302 South Clay Liberal, KS 67901

PHONE# (316) 624-4941 OPERATORS LICENSE NO. 5941

Character of Well Gas

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 2-5-98 (date)

by Steve Pfiefer (KCC District Agent's Name).

Is ACO-1 filed? YES If not, Is well log attached? _____

Producing Formation Morrow / ST LOUIS Depth to Top 5285' Bottom 6560 T.D. 6635

PBTD 3200

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				7	6631	1523
				9 5/8	719	
				DV tool @ 2900 w/ 200 sx		

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from _____ feet to _____ feet each section.

Mixed 4 sx bulls to 50 sx cmt. to plug unknown perfs. Tag top of plug @ 2480. Shot 7" loose @ 1523. Pulled to 740. Circ. hole w/ mud & mixed 50 sx plug 740 to 640. Pull 7" to 390. Mixed 50 sx plug 390 to 290. Pulled to 40. Mixed 10 sx plug 40 to 0. Cut off & capped 9 5/8 4 ft. below ground level.
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sargent And Horton Plugging, Inc. License No. 31151

Address Rt. 1, Box 49 BA Tyrone, OK 73951-9731


NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: ROSEL ENERGY, INC.

STATE OF KANSAS COUNTY OF Seward, ss.

George F. Rosel (Employee of Operator) or (Operator) above-described well, being first duly sworn on oath, says: That I have knowledge of the fact statements, and matters herein contained and the log of the above-described well as filed to the same are true and correct, so help me God.

(Signature) [Signature]

(Address) 302 S. Clay Ave., Liberal, KS 67901



SUBSCRIBER AND SWORN TO before me this 2 day of MARCH, 19 98

Betty J. Schroeder
Notary Public

My Commission Expires: January 19, 2000