

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-189-20983-0000

LEASE NAME Haworth #2 Unit

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

WELL NUMBER 4

3960 Ft. from S Section Line

4230 Ft. from E Section Line

SEC. 25 TWP. 34S RGE. 36 ~~For~~ (W)

COUNTY Stevens

Date Well Completed 3/18/87

Plugging Commenced 3/18/87

Plugging Completed 3/18/87

LEASE OPERATOR Mobil Oil Corporation

ADDRESS P.O. Box 5444, Denver, CO 80217

PHONE# (303) 298-2696 OPERATORS LICENSE NO. 5208

Character of Well Gas

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Kansas

Is ACO-1 filed? Yes If not, is well log attached? \_\_\_\_\_

Producing Formation PA Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. \_\_\_\_\_

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	1767	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_ feet to \_\_\_ feet each set.

See Back of Page

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Cheyenne Drilling, Inc. License No. 5382

Address Garden City, Kansas

STATE OF Colorado COUNTY OF Denver, ss.

J. E. Dawson (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]

(Address) P.O. Box 5444, Denver, CO 80217

SUBSCRIBED AND SWORN TO before me this 3rd day of June, 19 87

[Signature]  
Notary Public

My Commission Expires: 7/2/90 JUN 8 1987

6650-3379 9.2 Mud  
3379-3240 50 sx 60/40 POZ 6% Gel  
3240-2759 9.2 Mud  
2759-2589 50 sx 60/40 POZ 6% Gel  
2589-1798 9.2 Mud  
1798-1468 50 sx 60/40 POZ 6% Gel  
1468-899 9.2 Mud  
899-634 40 sx 60/40 POZ 6% Gel  
634-40 9.2 Mud  
40-3 10 sx 60/40 POZ 6% Gel  
15 sx in Rat hole 60/40 POZ 6% Gel  
10 sx in Mouse hole 60/40 POZ 6% Gel  
Cut off 8 5/8" csg 5' below ground level.

